

NOV 18 1997

COMMISSION

CLARE COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
#233-97
97 NOV -4 PM 3:16
REGISTER OF DEEDS
CLARE COUNTY
CAROL A. McAULAY

For corners in

<u>CLARE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>18N</u> R <u>6W</u>	<u>D-7</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, MARK R. ROBISON, in a field survey on July 1, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1848 Lyon
Set 1/4 Sec. Post
Wil.-Hemlock 10 N31 3/4E 11
Nor. Pine 11° S21W 41

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" x 18" rod 7 ft. South of centerline of gravel road opposite a fence corner to the North. Measured West 2660.30 ft. to C-7 and measured East 2659.80 ft. to E-7. Corner is on-line between section corners. GLO is 5318.94 C-7 to E-7.

See dossier for detailed report.

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County
Chairman [Signature]
Date 9-16-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" rod with Clare County Remonumentation Cap marked P.S.#27458. Accepted as best available evidence of accepted position of the corner.

Witnesses:
S02W 24.56', N&T, 19" W. Pine
N37W 64.16', N&T, 14" Twin Maple
S39W 50.88', N&T, 10" Triple Maple
S50E 51.18', N&T, 12" R. Pine

Signed by [Signature]
Surveyor's Michigan License No. 27458

Date 10-31-97

