

Survey &  
REMONUMENTATION

NOV 18 1997

CLARE COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>CLARE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>18N</u> R <u>6W</u>	<u>F-7</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECEIVED  
#234-97  
97 NOV -4 PM 3:16  
REGISTER OF DEEDS  
CLARE COUNTY  
CAROL A. McAULAY  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, MARK R. ROBISON, in a field survey on July 1, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1848 Lyon Set 1/4 Sec Post Wit.-Bl. Ash 8" S18 1/2W 50 Bl. Ash 10" N70W 21	10-20-80 Lapham LCRC#389 Set 1/2" C.I. Wit.-S20W 4.15 8" Ash East 3.52 4" Ash S45E 6.45 6" Hemlock West 12.65 6" Ash
06-06-80 Lapham survey notes of Section 16	
	4-7-94 Robison (132) 3-447 Wit.-same as LCRC#389 Measured 2684.62 East to G-7 (GLO 2673.0)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" x 18" C.I. and wood stake and three 1980 witnesses. Corner is approximately 140 ft. North of gravel road. (132) 3-447 shows road 70 ft. +/- South of 1/8 corner. 06-06-80 survey notes indicate corner was set S.P.M. between section corners, 2694.01 ft. from E-7 and 2694.01 ft. from G-7.

APPROVED LAND CORNER  
P.A. 345 of 1990  
Clare County

See dossier for detailed report.

Chairman Paul H. Lippman  
Date 9-16-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" rerod with Clare County Remonumentation Cap marked P.S.#27458. Accepted as best available evidence of the accepted position of the corner.

Witnesses:  
S20W 4.15', N&T, 8" Ash (OBT)  
East 3.52', N&T, 6" Ash (OBT)  
West 12.65', N&T, 6" Ash (OBT)  
N28E 11.20', N&T, 3" Ash

Signed by Mark R. Robison  
Surveyor's Michigan License No. 27458

Date 10-31-97

