

NOV 18 1997

CLARE COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

CLARE

(County)

Located in:

Corner Code #

- 1. Public Land Survey T 18N R 6W H-7
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, MARK R. ROBISON, in a field survey on July 1, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1848 Lyon
Set 1/4 Sec. Post
Wit.-Maple 11" S67 1/2E 20
 Birch 14" N46W 44

11-10-82 Fluharty LCRC#424
Wit.-same as (132) 2-749

11-02-82 Fluharty (132) 2-749 & 2-750
Fd. 3/4" Pipe at Int. C.L.
Wit.-N47W, 57.90 8" Oak
 S12E 50.56 P.P.
 S15W 20.50 W. edge W. Post of Sign

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" x 20" pipe in clay tile and all 1982 witnesses at intersection of T-road North. Measured West 2582.96 to G-7 per Fluharty. Measured East 2622.05 to I-7.

See dossier for detailed report.

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County

Chairman Paul D. Lyle
Date 9-16-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" rerod with Clare County Remonumentation Cap marked P.S.#27458 in old clay tile. Accepted as best available evidence of the accepted position of the corner.

Witnesses:
N47W 57.90', N&T, 12" Oak (OBT)
S12E 50.56', N&T, P.P. (OBT)
N38E 89.28', N&T, 8" B. Cherry
N14W 90.94', N&T, 9" R. Oak

Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 10-31-97



Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													