

**SURVEY &  
REMONUMENTATION**

**MAR 24 2000**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
Clare County Remonumentation**

**SECTION**

For Corners in <u>Clare</u> (County)	Located In:	Corner Code#:
1. Public Land Survey	T. <u>19N</u> R. <u>6W</u>	<u>I-13</u>
	T. <u>18N</u> R. <u>6W</u>	<u>I-1</u>
	T. _____ R. _____	_____
2. Public Controlling in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
3. Miscellaneous Property in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

199900009774  
Filed for Record in  
CLARE COUNTY MICHIGAN  
CAROL MCAULAY  
On 11-10-1999 At 01:30 pm.  
LAND CORNER 9.00  
OR Liber 2 Page 53 - 53

Instrument Liber Page  
199900009774 OR 2 53

# 364-99

**Register of Deeds Stamp & File Number**

I, Mark R. Robison, in a field survey on August 11, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**  
This is a single common corner to  
T19N, R6W, I-13 and T18N, R6W, I-1

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1838 Rousseau  
Set Post Cor 34-35  
Pine 30" N80W 29  
Hemlock 10 N20E 41
- 10-01 Harper, CSR 1-08 & 4-09  
Cedar Stake  
N16E 27.1. 24" W. Pine Stp.  
I-1 to G-1, 78.36
- 8-24-06 & 1-23-07 Johnson  
CSR 4-66 & 4-81  
N54E, 50, 36" W. Pine  
I-1 to K-1 78.80
- 9-38 Unknown, CSR 2-105  
Stake Tile  
I-1 to H-1 39.75
- Circa 1900, CSR 6-251  
I-13 to H-13, 39.91
- 1962 Lapham, CSR 6-35  
Little Norway Lake Subdivision
- 10-85 Lapham, CSR 16-48  
Lakeshore Subdivision
- 8-16-90 Robison, CSR 611-189  
Fd 3/4" Iron  
N45E 61.43 F. Post  
S10E 25.8 6" Elm  
S15W 27.29 15" Elm  
S60W 58.57 15" Elm
- 12-30-92 Erickson LCRC #738  
Fd C.I. 9433 in C.L. gravel rd int.  
S10E, 25.61 Nail in 8" Elm  
S42W 27.21 Nail in 15" Elm  
S76W 58.57 Nail in 15" Elm  
N59E 61.38 Nail in Cor. F. Post

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

See dossier for detailed report.  
Found C.I. Excavated to 3' and found no other material. Found all 1990 & 1992 witnesses. Corner falls in gravel road on a steep hillside with about 10 feet fill at C.L. Meas. East 2629.04 to J-13 and West 2615.70 to H-13. Meas. 996.5 (Rec 997.27) to P.O.B. Little Norway Lkae Subd.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Set 5/8" x 36" rered with Clare Co. Remon Cap marked P.S. #27458. Accepted as best available evidence of the accepted position of the corner.

- Witnesses:  
N68°E, 61.50; Spike in Fence Cor. Post (OBT)  
S10°E, 25.61; Spike in 12" Elm (OBT)  
S42°W, 27.12; Spike in 18" Elm (OBT)  
S73°W, 58.63; Spike in 24" Elm (OBT)

Signed by Mark R. Robison  
Surveyor's Michigan License No. 27458



**APPROVED LAND CORNER**  
P.A. 345 of 1990  
Clare County  
Chairman Paul D. Laska  
Date 9-29-99

Date 11-8-99

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971