

NOV 18 1997

CLARE COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>CLARE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>18N</u> R <u>6W</u>	<u>1-7</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECORDED
✓
E237-97
97 NOV -4 PM 3:16
REGISTER OF DEEDS
CLARE COUNTY
CAROL A. McLAULAY

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, MARK R. ROBISON, in a field survey on July 1, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1848 Lyon
Set Post Cor. Sec. 14, 15, 22, 23
Wit.-Hemlock 14" N78 3/4W 15
Hemlock 24" N57 1/2E 31
- 11-10-82 Fluharty L.C.R.C.#424
Fd. 1 1/2" Pipe at Int.
Wit.-N20E 33.97 F. Post
N30W 37.89 4" Poplar
S30E 34.28 W. edge Yield Sign
- 6-15-07 Johnson CSR 4-107 & 6-195
Wit.-Pine Stump 36" N2W 164
Pine Stump 36" N22W 172 1/2
I-7 to K-7 - 80.59

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/2" x 18" pipe in old clay tile and two 1982 witnesses. Did not find CSR witnesses.

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County

Chairman Paul D. Laska
Date 9-16-97

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" rod with Clare County Remonumentaton Cap marked P.S.#27458 in old clay tile. Accepted as best available evidence of perpetuation of CSR Corner.

- Witnesses:
- N20E 33.97', N&T, F. Post (OBT)
 - S30E 35.40 West edge Yield Sign (OBT)
 - N39W 85.14', N&T, 5" Maple
 - S50W 53.04', N&T, Corner Fence Post
 - N08W 88.98', N&T, 6" Balsam



Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 10-31-97