

**SURVEY &
REMONUMENTATION**

JAN 23 2001

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Clare County Remonumentation**

For Corners in
Clare

(County)

Located In:

Corner Code#:

- | | | |
|---|----------------------------|------------|
| 1. Public Land Survey | T. <u>18N</u> R. <u>6W</u> | <u>L-5</u> |
| | T. _____ R. _____ | _____ |
| | T. _____ R. _____ | _____ |
| 2. Public Controlling
in Section | S. _____ T. _____ R. _____ | _____ |
| | S. _____ T. _____ R. _____ | _____ |
| 3. Miscellaneous
Property in Section | S. _____ T. _____ R. _____ | _____ |
| | S. _____ T. _____ R. _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

200000010141
Filed for Record in
CLARE COUNTY MICHIGAN
CAROL MCAULAY
On 12-15-2000 At 07:44 am.
LAND CORNER 9.00
OR Liber 2 Page 264 - 264

Instrument Liber Page
200000010141 OR 2 264

#469-00

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on May 19, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO
Lyon, 1848
Beech 9" N3 1/4°W, 34 LINKS
Norway Pine 18" S73°E, 21 LINKS

Survey, Lapham, 1987 L3. Pg. 27
Same as LCRC #557-87
L-5 to K-5 = 2666.04

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County

Chairman Paul S. Lapham
Date 9-18-00

Lapham, 1987, LCRC #557-87
Found R/R Spike, 3 witnesses

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner.

No GLO evidence found. Found R/R spike and cement nail at surface. Excavated to a depth of 2' and nothing else found. Spike is 0.5' South of centerline E-W Road (Mannsiding) and on line with fence to South. 3-1987 witnesses found. Meas. 2666.04 to K-5 and 2663.80 to M-5. No evidence of other position for corner. Accepted found spike as best available evidence of position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set 5/8" x 36" rod with Clare County Remon Cap marked P.S. #27458 in Monument Box.

Witnesses:

- South, 30.45' - N & T in Corner Fence Post (OBT)
- S54°W, 36.85' - N & T in 27" Maple (OBT)
- N20°W, 35.50' - N & T in 12" Pine (OBT)
- N20°E, 59.50' - N & T in 18" x 18" x 24" Maple



Signed by

Mark R. Robison

Date

12/14/2000

Surveyor's Michigan License No. 27458