

SURVEY & REMONUMENTATION

JAN 23 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Clare County Remonumentation

For Corners in
Clare

(County)

Located In:

Corner Code#:

- 1. Public Land Survey T. 18N R. 5W A-5
 T. 18N R. 6W M-5 ✓
 T. _____ R. _____
- 2. Public Controlling S. _____ T. _____ R. _____
 in Section S. _____ T. _____ R. _____
- 3. Miscellaneous S. _____ T. _____ R. _____
 Property in Section S. _____ T. _____ R. _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

200000010143
 Filed for Record in
 CLARE COUNTY MICHIGAN
 CAROL MCAULAY
 On 12-15-2000 At 07:44 am.
 LAND CORNER 9.00
 OR Liber 2 Page 266 - 266

Instrument Liber Page
 200000010143 OR 2 266

#471-00

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on May 19, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

This is a single corner common to T18N, R5W, & T18N, R6W.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO
 Lyon, 1848
 Beech 10" N57°W, 10 LINKS
 Beech 10" S43°W, 12 LINKS
 Beech 10" S33°E, 16 LINKS
 Maple 6" N43°W, 38 1/2 LINKS
 C.S.R, Harper, 1902, Bk 1. Pg. 12
 & Bk. 4 Pg. 14
 W. Pine Stub 20" S18 1/2°W, 47 LINKS
 W. Pine Stump 18" N27°E, 75 LINKS
- Lapham, 1992 LCRC #669-92
 Found P.K. Nail, 4 witnesses
- Lapham, 1995, LCRC #770-95
 Found P.K. Nail, 4 witnesses with
 2 the same as LCRC #669-92
- Survey, Robison, 1993 L3. Pg. 477
 Same as LCRC #770-95
 B-5 to A-5 = 2544.94 (GLO = 2514.6)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner.

No evidence of GLO survey found. Found spike and excavated to 2' and found nothing else. Found 3 witnesses from LCRC #770-95 with 1 in good shape. Measured to B-5 as 2544.58' to A-4 as 2636.77', to A-6 as 2622.67' and to L-5 (18N6W) as 2663.88'. Corner is 5' South of centerline East-West road (Mannsiding) and on centerline road to South (Hemlock). No evidence of another corner found. Accepted found spike as best available evidence of position of corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8"x 36" rered with Clare County Remon Cap marked P.S. #27458 in Monument Box.

Witnesses:

- N55°W, 45.95' - Center of telephone riser (OBT)
- N45°E, 53.76' - N & T in Fence Post
- S63°E, 74.58' - N & T in Power Pole
- S48°W, 49.94' - N & T in 17" Balsam

Signed by Mark R. Robison
 Surveyor's Michigan License No. 27458



APPROVED LAND CORNER
 P.A. 345 of 1990
 Clare County

Chairman Paul H. Lym
 Date 9-18-00

Date 12/14/2000