

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF-- | LOCATED IN-- | CORNER CODE NUMBER |
|---|--|----------------------|
| 1. PUBLIC LAND SURVEY _____ | T. <u>18</u> N. R. <u>06</u> W. | <u>B-1, B-2, B-3</u> |
| 2. PROPERTY CONTROLLING IN SECTION <u>6</u> | T. <u>18</u> N. R. <u>06</u> W. | <u>11, 16</u> |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | T. _____ N. R. _____ E. S. R. _____ W. | _____ |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, CARL F. ROSER, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on DECEMBER 14, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

C. (CONTINUED)

| | |
|--|---|
| 11 | 16 |
| SET 5/8" X 34" REROD W/RLS CAP & CED POST W/LOC TAG. | FD SHORT SUCKER ROD REPLACED W/ 1" X 57" PIPE W/FD RLS CAP. |
| 7" MAPL, CLUMP N45°E 38.2' | 4" CEDAR S60°E 12.3' |
| 7" B OAK S45°E 14.5' | 3" CEDAR N30°W 11.1' |
| 6" MAPL, CLUMP S40°W 6.0' | 7" CEDAR N75°E 24.7' |
| 8" ASH N50°W 27.0' | 10" HEMLOCK S20°W 27.7' |
| | CTR M-115 N88°W 228' |
| | FD SUCKER ROD W/ MCCLUNG RLS CAP - N88°W 120.5' |

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**
- B-1 FD & ACCEPTED 1" PIPE BY RLS, MATT MCCLUNG FOR 1/4 COR. COR FITS S.P. TO U.S. BETW NW SEC 6 (CALC IN RV) & NE SEC 6. COR IS A RESULT OF MCCLUNG'S WORK IN SEC 6 (18-6) & SEC 31 (19-6).
 - B-2 ESTAB CTR OF SEC 6 AT INTERSEC OF ONE-QTR LINES.
 - B-3 RE-ESTAB S 1/4 COR OF SEC 6 ON LINE BETW SW & SE COR'S OF SEC 6 & AT PRO-RATED DISTANCE TO U.S. (RUN-OUT SEC). FITS FD MCCLUNG 1/8 COR 1/4 MILE EAST.
 - 11 ESTAB CTR OF SW 1/4 OF SEC 6 (RUN-OUT SEC) PER STD B.L.M. INSTRUCTIONS.
 - 16 FD SHORT SUCKER ROD FOR SW COR OF E 1/2 OF SE 1/4 OF SEC. 6.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| | | |
|---|--|---------------------------------|
| B-1 | B-2 | B-3 |
| FD 1" PIPE W/MCCLUNG RLS CAP; ADDED CED POST. | SET 5/8" X 34" REROD W/RLS CAP & CED POST W/LOC TAG. | SET DNR MON & CED POST 9" & 10" |
| 10" B OAK N60°W 53.2' | 12" MAPLE N10°W 20.4' | MAPLE N70°W 26.0' |
| 18" TW B OAK N35°E 28.2' | 8" MAPLE N35°E 36.2' | 9" MAPLE N45°E 15.7' |
| 8" B OAK S10°E 34.2' | 5" MAPLE S30°E 20.6' | 12" MAPLE S30°E 26.1' |
| 7" B OAK S50°W 49.9' | 3" MAPLE S55°W 34.1' | 14" MAPLE S40°W 27.3' |
| CTR TRAIL RD DUE W 257' | | CTR M-115 DUE E 1082' |

SIGNED BY Carl F. Roser DATE 01-06-86

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. _____



(SEAL)
FREEMAN TWP.
CLARE COUNTY