

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 18 N. R. 06 E-4	E-4
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S. R. _____ E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION 8 _____	T. 18 N. R. 06 E-4	::3985.2' S OF D-3. :::980.7' N OF D-5. ::::899.5' E OF D-5.
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, CARL F. ROSER, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on FEBRUARY 7, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

C. (CONTINUED)

FD 5/8" IR ROD W/RLS CAP;
 ADDED CED POST W/LOC TAG.
 16" W PINE N55°W 3.72
 12" MAPLE IN
 CLUMP 3 S30°E 26.31
 CTR M-115 DUE E 93.3'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

E-4 FD & ACCEPTED 1 1/2" PIPE BY RLS, M. MCCLUNG FOR E 1/4 COR OF SEC 8. AN OLD LOOKING 5/8" ROD WAS FD 4'±E OF CTR OF N-S RD, SAID ROD BEING S53°34'E, 62.2' FROM 1 1/2" PIPE.

:: FD 5/8" IR W/RLS CAP, M.MCCLUNG, ON INTERSEC OF N-S 1/4 LINE OF SEC 8 & N'LY R.O.W. LINE OF M115.


::: FD 5/8" IR W/RLS CAP, M.MCCLUNG, ON INTERSEC OF N-S 1/4 LINE OF SEC 8 & S'LY R.O.W. LINE OF M115.

:::: FD 5/8" ROD W/RLS CAP, M.MCCLUNG, ON S LINE OF SEC 8 INTERSEC W/W'LY R.O.W. LINE OF M115.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FD 1 1/2" PIPE W/RLS CAP; ADDED CED POST W/LOC TAG. 3" MAPLE N45°E 9.9' 14" MAPLE S25°W 35.2' 3" BALSAM S85°W 20.1' CTR N-S GR RD DUE E 49' DRY CREEK BED DUE S 98'±5'	FD 5/8" IR ROD W/RLS CAP; ADDED CED POST W/LOC TAG. 6" MAPLE N30°W 17.0' 7" MAPLE N60°E 10.7' CTR M115 DUE S 102'	FD 5/8" IR ROD W/RLS CAP; ADDED CED POST W/LOC TAG. 4" BALSAM N30°W 14.7' 6" BALSAM N75°E 5.5' CTR M115 DUE N 103'
--	---	--

SIGNED BY Carl F. Roser DATE 01-13-86
 SURVEYOR'S MICHIGAN REGISTRATION NO. 12028



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)
 FREEMAN TWP.
 CLARE COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. _____