

SURVEY & REMONUMENTATION

JAN 23 2001

SECTION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Clare County Remonumentation

For Corners in
Clare
 (County)

Located In: Corner Code#:

1. Public Land Survey T. 19N R. 4W C-13
 T. 18N R. 4W C-1 ✓
 T. _____ R. _____ C-_____
 2. Public Controlling S. _____ T. _____ R. _____
 in Section S. _____ T. _____ R. _____
 3. Miscellaneous S. _____ T. _____ R. _____
 Property in Section S. _____ T. _____ R. _____
 4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

200000009273
 Filed for Record in
 CLARE COUNTY MICHIGAN
 CAROL MCAULAY
 On 11-14-2000 At 11:04 am.
 LAND CORNER 9.00
 OR Liber 2 Page 199 - 199

Instrument Liber Page
 200000009273 OR 2 199

404-00

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on April 20, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

This is a single corner common to T19N, R4W, & T18N, R4W.

A. Description of original monument and accessories and/or subsequent restoration:

GLO, Nicholson, 1838 Pine 6" N33 1/2°E, 18 LINKS Pine 6" N66°W, 40 LINKS	CSR Arthur Johnson, 1912 CSR, Bk. 2. Pg. 22 Pine 36" S41 1/2°E, 56 LINKS Oak 8" N24 1/2°E, 89 LINKS C-13 to B-13 - 40.06	CSR, Bk. 6 Pg. 248 Pine 6" N33 1/2° E 18 LINKS
GLO, Cannon, 1856 W. Pine 30" S34°E, 60 LINKS Hemlock 14" S84 1/2°W 90 LINKS	CSR, Bk. 6 Pg. 247 Pine 36" S 41 1/2°E, 56 LINKS Oak 8' N24 1/2°E 89 LINKS C-13 to B-13 - 40.00	Surveys None Lapham, 1989 LCRC #594-89 Fd 1/2 Iron, 4 witnesses See Section C

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Fd 1/2" Iron in Mon. Box. and 4 witnesses from LCRC #594-89. Measured 2643' C-13 to B-13, & 2632' C-13 - D-13. Accepted iron in Mon. Box as best available evidence of the accepted position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" rerod with Clare County Remon Cap marked P.S. #27458 in Mon. Box.

Witnesses:
 S70°E, 69.90' - N & T 42" Maple (OBT)
 S85°W, 67.45' - N & T P. Pole (OBT)
 N70°E, 75.83' - N & T 14" x 12" Maple (OBT)
 West, 26.75' - Center of T. Rise (OBT)

APPROVED LAND CORNER
 P.A. 345 of 1990
 Clare County
 Chairman Mark R. Robison
 Date 8-30-00



Signed by Mark R. Robison
 Surveyor's Michigan License No. 27458

Date 11-13-2000