

SURVEY & REMONUMENTATION

JAN 23 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Clare County Remonumentation

200000009276
 Filed for Record in
 CLARE COUNTY MICHIGAN
 CAROL MCAULAY
 On 11-14-2000 At 11:04 am.
 LAND CORNER 9.00
 OR Liber 2 Page 202 - 202

For Corners in
Clare
 (County)

Located In: Corner Code#:

1. Public Land Survey T. 18N R. 4W F-1 ✓
 T. 19N R. 4W F-13
 T. _____ R. _____
 2. Public Controlling S. _____ T. _____ R. _____
 in Section S. _____ T. _____ R. _____
 3. Miscellaneous S. _____ T. _____ R. _____
 Property in Section S. _____ T. _____ R. _____
 4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Instrument Liber Page
 200000009276 OR 2 202

#407-00

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on May 4, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

This is a single corner common to T18N, R4W, & T19N, R4W.

A. Description of original monument and accessories and/or subsequent restoration:

GLO
 Nicholson, 1838
 Aspen 8" N40°E, 07 LINKS
 B. Oak 6" N30°W, 10 LINKS
 C.S.R., Unknown, Bk. 6 Pg. 249
 Blk. Oak 18" N23°E, 13 LINKS
 Pine Stump 18" N70°W, 15 LINKS
 LCRC, Lapham, 1974 #170-74
 Found well point, 3 witnesses
 LCRC, Sedgman, 1977 #298-77
 Found concrete monument, same
 3 witnesses as LCRC #170-74

Plat of Forest Highlands, Batzer, 1975, L. 15. Pg.9-12
 Concrete monument for corner
 Survey, Batzer, 1975 L1. Pg. 935
 Same as LCRC #170-74
 Survey, Batzer, 1975, L1. Pg. 937
 Same LCRC #170-74
 Survey, Sedgman, 1977, L2. Pg. 331
 Same as LCRC #298-77

APPROVED LAND CORNER
 P.A. 345 of 1990
 Clare County
 Chairman Paul B. Lapham
 Date 8-30-00

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner.
 No GLO or CSR evidence found. Found concrete monument with 1 1/2" x 36" well point beside it. Excavated to 3' nothing else found and no evidence of other corners found. Remains of all 3 witnesses found. Accepted concrete monument as best available evidence of accepted position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" rered with Clare County Remon Cap marked P.S. #27458.
 Witnesses:
 N39°W, 14.85' - N & T in 10" Red Oak
 N58°E, 37.45' - N & T in 16" Red Oak
 S30°W, 18.30' - N & T in 12" x 12" Red Oak
 S70°E, 17.23' - N & T in 7" Maple

Signed by Mark R. Robison
 Surveyor's Michigan License No. 27458

Date 11-13-2000

