

CLARE COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
E 10 A 1
#187-96
96 DEC 23 AM 11:59
REGISTER OF DEEDS
CLARE COUNTY
DONNA M. CARR

For corners in

CLARE (County)	Located in:	Corner Code #
1. Public Land Survey	T 18N R 4W	G - 7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, MARK R. ROBISON, in a field survey on November, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1856 CANNON S15W 99.95 24" STUMP
WIT.-HEMLOCK 12" N57 1/2E 21L N10W 8.55 3" OAK
B. OAK 16" S60W 27L (SEE ATTACHED NOTES RE: S.P.M.)

NO CO. SURVEY RECORDS FOUND 11-29-89 LAPHAM.LCRC
UNDATED MSHD NOTES-NO CORNER FOUND FOUND CONC MONUMENT
WIT.-SAME AS 5-27-88 SURVEY

5-27-88 LAPHAM (132) SURVEY
SET CAPPED IRON
WIT.-S45E 68.90 30" OAK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CONCRETE MONUMENT AND ALL 1988 WITNESSES EXCEPT 24" STUMP IS BADLY DETERIORATED.

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County
Chairman Paul M. Lapham
Date 11-14-96

SEE DOSSIER FOR DETAILED REPORT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-7: CORNER COMMON TO SECTIONS 15, 16, 21 & 22
ACCEPTED 4" CONCRETE MONUMENT AS CLARE COUNTY MONUMENT. ACCEPTED AS BEST AVAILABLE EVIDENCE OF ACCEPTED POSITION OF CORNER.

WITNESSES:
S45E 68.90 N&T IN 36" OAK (OBT)
N19W 8.55 N&T IN 10" OAK (OBT)
S11W 181.08 N&T IN TWIN 18"-30" OAK
S71W 131.48 N&T IN 24" MAPLE

Signed by Mark Robison
Surveyor's Michigan License No. 27458

Date 12-20-96

