

CLARE COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
E 11 11 31
#188-96
96 DEC 23 AM 11:59
REGISTER OF DEEDS
CLARE COUNTY
DONNA M. CARR

For corners in

| CLARE (County) | Located In: | Corner Code # |
|---------------------------------------|-------------|---------------|
| 1. Public Land Survey | T 18N R 4W | 1 - 7 |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, MARK R. ROBISON, in a field survey on November, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

| | |
|---|---|
| 1856 CANNON WIT.-MAPLE 10" N78E 33L Y. PINE 15" S55W 22L 9-28-06 JOHNSON GOVT CORNER FOUND CSR (BK 5) WIT.-PINE 24 N31E 94L MAPLE 3 S26 1/2E 144L MSHD-NOTES AND R/W MAP MEAS 2625.39 W TO H-7 7-19-74 LAPHAM | FOUND MON BOX WIT.-S85E 71.40 POW POLE S85W 72.25 POW POLE N40W 107.15 TELE POLE 9-5-88 PAUL LAPHAM FILES DWG INDICATES MEAS. W 2647.88 TO H-7 1-26-49 GOGGIN-PLAT HATTON ACRES 1-30-64 LAPHAM-PLAT WOODLAND ACRES |
|---|---|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" X 20" REROD IN MON BOX IN HWY. FOUND TWO 1974 WITNESSES. CORNER FITS PLATS OF HATTON ACRES & WOODLAND ACRES.

SEE DOSSIER FOR DETAILED REPORT.

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County
Chairman Paul Sepko
Date 11-14-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-7: CORNER COMMON TO SECTIONS 14, 15, 22 & 23
SET 5/8" X 36" REROD WITH 3" CLARE COUNTY MONUMENT CAP. ACCEPTED AS BEST AVAILABLE EVIDENCE OF ACCEPTED POSITION ON THE CORNER.

WITNESSES:
S74E 71.40' N&T IN P.P. (OBT)
S81W 72.25' N&T IN P.P. (OBT)
S32W 131.02' N&T IN 12" R. PINE
N46E 132.70' N&T IN R. OAK

Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 12-20-96

