

**SURVEY &  
REMONUMENTATION**

**JAN 23 2001**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
Clare County Remonumentation**

For Corners in  
Clare

(County)

Located In:

Corner Code#:

- |   |                            |       |
|---|----------------------------|-------|
| 1. Public Land Survey                   | T. <u>19N</u> R. <u>4W</u> | J-13  |
|   | T. <u>18N</u> R. <u>4W</u> | J-1 ✓ |
|   | T. _____ R. _____          | _____ |
| 2. Public Controlling<br>in Section     | S. _____ T. _____ R. _____ | _____ |
|   | S. _____ T. _____ R. _____ | _____ |
| 3. Miscellaneous<br>Property in Section | S. _____ T. _____ R. _____ | _____ |
|   | S. _____ T. _____ R. _____ | _____ |
| 4. Lot No. _____, Recorded Plat         |                            |       |
| 5. Private Claims _____                 |                            |       |

200000009280  
Filed for Record in  
CLARE COUNTY MICHIGAN  
CAROL MCAULAY  
On 11-14-2000 At 11:04 am.  
LAND CORNER 9.00  
OR Liber 2 Page 206 - 206

Instrument Liber Page  
200000009280 OR 2 206

*441-00*

**Register of Deeds Stamp & File Number**

I, Mark R. Robison, in a field survey on May 9, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

This is a single corner common T18N, R4W. & T19N, R4W.

A. Description of original monument and accessories and/or subsequent restoration:

GLO  
Nicholson, 1838  
15" Cedar for corner

LCRC  
Sedgman, 1975 #230-76  
Found spike, reset 1/2" capped bar  
3 witnesses

Private Files - Lapham, 1975  
I-1 to J-1 = 2643.92  
J-1 to K-1 = 2643.78

C.S.R.  
Moore, 1958, Bk. 3 Pg. 47 & 93  
Corner per sketch in book  
Set monument 75'  
South of centerline  
I-1 to J-1 = 2643.8  
J-1 to K-1 = 2643.8

**APPROVED LAND CORNER**  
P.A. 345 of 1990  
Clare County

Chairman *Paul B. Lapham*  
Date 8-30-00

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

No GLO evidence found. Found 1/2" x 18" capped iron in Mon. Box in centerline of M-61. New guard rails placed so all 1975 witnesses are gone. No other evidence of corners found. 1958 CSR matches with 1975 Lapham measurements and current measurements, measured West 2643.92 to I-1 & East 2643.78 to K-1. Accept found iron as best available evidence accepted position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" rerod in Mon. Box with Clare County Remon Cap marked P.S. #27458.  
Witnesses:  
N45°E, 30.42' - N & T in top of guard rail post  
North, 20.96' - N & T in top of guard rail post  
N45°W, 25.52' - N & T in top of guard rail post  
S55°E, 102.80' - 1/2" Iron



Signed by *Mark R. Robison*  
Surveyor's Michigan License No. 27458

Date 11-13-2000