

CLARE COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
E 17 17
#190-96
96 DEC 23 AM 11:59

REGISTER OF DEEDS
CLARE COUNTY
DONNA M. CARR

For corners in

| | | |
|---------------------------------------|--------------------------|---------------|
| <u>CLARE</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>18N</u> R <u>4W</u> | <u>K - 7</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, MARK R. ROBISON, in a field survey on November, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 16 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

| | |
|---|---|
| 1856 CANNON WIT.-HEMLOCK 26" N43E 41 L BEECH 12" S73W 15 L | MEAS N 39.69 1/2 TO K-6 |
| 09-28-06 JOHNSON GOVT CORNER FOUND | 12-24-06 JOHNSON WIT.-SAME AS ABOVE MEAS E 40.06 TO L-7 |
| 11-10-06 JOHNSON WIT.-PINE STUMP 36" S33W 113 PINE STUMP 30" N50E 50 MEAS S 39.86 TO K-8 | |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND GUN BARREL AT CORNER. FOUND 36" PINE STUMP S33W 74.58. FOUND REMAINS OF 36" PINE STUMP N50E 36.3 FEET. FOUND FENCE CORNER WITH OLD W.W. FENCE RUNNING EAST, SOUTH & NORTH, 36 1/2 FEET SOUTH AND 30 FEET EAST OF CORNER. MEAS. EAST 2628.53 TO L-7 (CSR 2643.96). MEAS WEST 5304.24 TO L-7.

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County

Chairman Paul M. [Signature]
Date 11-14-96

SEE DOSSIER FOR DETAILED REPORT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-5: CORNER COMMON TO SECTIONS 13, 14, 23, 24
SET 5/8" X 36" REROD WITH 3" CLARE COUNTY MONUMENT CAP. ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE PERPETUATION OF THE C.S.R. CORNER.
WITNESSES:
N88E 26.00 N&T IN 20" BEECH
N14E 36.90 N&T IN 6" ASH
SOUTH 40.30 N&T IN 15" W. OAK
N70W 69.87 N&T IN 24" R. OAK
S33W 74 1/2 OLD 36" PINE STUMP (OBT)
N50E 36 REMAINS OF PINE STUMP (OBT)



Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 12-20-96