

SURVEY & REMONUMENTATION COMMISSION
APR 06 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
 E 10 A D
 # 170-94
 94 NOV 28 AM 10:36
 REGISTER OF DEEDS
 CLARE COUNTY
 DONNA M. CARR

For corners in

CLARE
 (County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>18N</u>	R	<u>5W</u>	<u>A-7</u>
	T	<u>18N</u>	R	<u>6W</u>	<u>M-7</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	_____
	S	_____	T	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, MARK R. ROBISON, in a field survey on OCTOBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1838; NICHOLSON, POST (1)BEECH 12" N52°W 13 (2)HEMLOCK 8" S55 1/2°W 6 G.L.O.
 3-29-02 W.W.HARPER, (3)W. PINE STUB 20" S18 1/2°W 47 (4)W. PINE STUMP 18" N27°E 75 C.S.R. 11-1
 2-3-68, MOORES, PLAT OF WOODLAND HEIGHTS. L-9, PG. 7-10
 12-19-79 WILCOX, FOUND 1/2" IRON PIPE (5)TWIN OAK 8" S52°E 54.00' (6)TWIN OAK 8" S20°E 64.47'
 (7)TRI. OAK 4" S46°W 43.46' (8)OAK 6" S73°W 71.75'
 (9)IN CENTERLINE N-S RD. (10)10' S CENTERLINE E-W RD. L.C.R.C. 373

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FOUND 1/2"x30" GALV. PIPE, FOUND 5,6,7,8,9, & 10
 SEE WOODLAND HEIGHTS SUBDIVISION.- FOUND CONC. MON. S45°W 46.72'. EXCAVATED TO DEPTH OF THREE FEET.
 FOUND NO FURTHER EVIDENCE.

APPROVED LAND CORNER
 P.A. 345 of 1990
 Clare County
 Chairman Paul A. Lippman
 Date Nov. 23, 1994

This Corner established in Clare County Remonumentation Program.
 See dossier for detailed report.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 SET 5/8" X 36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP IN MONUMENT BOX.
 WITNESSES:
 N60°W, 165.78' - NAIL & TAG IN 15" NORWAY PINE
 S45°W, 46.72' - CONC. MONUMENT
 S52°E, 54.00' - NAIL IN TWIN 10" OAK (5)
 S73°W, 71.75' - NAIL & TAG IN 10" OAK (8)



Signed by Mark R. Robison Date 11-23-94

Surveyor's Michigan License No. 27458