

SURVEY & REMONUMENTATION

JAN 23 2001

SECTION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Clare County Remonumentation

For Corners in
Clare

(County)

Located In:

Corner Code#:

- 1. Public Land Survey T. 18N R. 5W B-5
T. _____ R. _____
T. _____ R. _____
- 2. Public Controlling S. _____ T. _____ R. _____
in Section S. _____ T. _____ R. _____
- 3. Miscellaneous S. _____ T. _____ R. _____
Property in Section S. _____ T. _____ R. _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

200000009699
Filed for Record in
CLARE COUNTY MICHIGAN
CAROL MCAULAY
On 11-29-2000 At 10:31 am.
LAND CORNER 9.00
OR Liber 2 Page 229 - 229

Instrument Liber Page
200000009699 OR 2 229

#434-00
Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on May 19, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO, Cannon, 1856
Y. Pine 15" S73°W, 41 LINKS
Y. Pine 23" N62°E, 35 LINKS

Gray, 1995 LCRC #762-95
Fd P.K. Nail 1.5 +/- North of centerline
at drive to North. 5 witnesses

C.S.R. Harper, 1902, Bk. 1 Pg. 12
& Bk. 4 Pg. 14
Tamarack 8" N50°E, 7 1/2 LINKS

Lapham, 1995, LCRC #770-95
Fd P.K. Nail, 4 witnesses same as
LCRC #762-95

Sub. - Holmes Development No. 1
Lapham, 1963 L7. Pg. 21
B-5 on centerline Meadow Croft Drive
From work sheets B-5 to C-5 = 2642'

Survey, Robison, 1993, L3. Pg. 477
Same as LCRC #770-95
B-5 to A-5 = 2544.94

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County
Chairman Paul Sept
Date 8-30-00

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner.

No evidence of GLO corner found. No evidence of CSR corner found. Found P.K. Nail 1.5' North of centerline. Excavated to 3' and nothing else found. No evidence of other corner positions found. Distance to A-5 measured as 2544.58', and to C-5 as 2641.60', distances verify corner from subdivision and 1963 and 1993 survey. Found 4 witnesses from LCRC #770-95. Accepted found P.K. Nail as best available evidence of position of corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set 5/8" X 36" rerod with Clare County Remon Cap marked P.S. #27458.

Witnesses:
N45°E, 41.13' - N & T in Power Pole (OBT)
N10°W, 90.50' - N & T in 12" R. Oak (OBT)
N45°W, 74.00' - N & T in 16" Cherry (OBT)
South, 36.65' - N & T in Maple Clump (OBT)



Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 11-28-2000