

**SURVEY & REMONUMENTATION COMMISSION**  
 For corners **APR 06 1995**

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED  
 E 10 AD  
 #75-94  
 94 DEC 29 AM 8:47

REGISTER OF DEEDS  
 CLARE COUNTY  
 DONNA M. GARR

CLARE (County) Located In: Corner Code #

1. Public Land Survey T18N R5W B-7  
 T R  
 T R  
 T R

2. Property Controlling S T R  
 in Section S T R

3. Miscellaneous S T R  
 Property in Sec. S T R

4. Lot No. , Recorded Plat

5. Private Claims

Register of Deeds Stamp & File Number

I, MARK R. ROBISON in a field survey on DECEMBER, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7	●											
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1856 CANNON, G.L.O.  
 POST (NOTE STATES OLD CORNER IS N18°E 382 LINKS)  
 WIT.-HEMLOCK 12" N23°W 37 LKS.  
 TAMARACK 10" S65°E 46 LKS.

C.S.R. NONE  
 NO RECORDED SURVEYS  
 NO L.C.R.C.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NO EVIDENCE OF CORNER. TRAVERSED AROUND SECTION 18 AND SET POINT ON SINGLE PROPORTIONATE MEASURE BETWEEN A-7 & C-7. G.L.O. MEASURE IS 80.76 (5330.16). WE MEASURE 5248.23. WE SET C-7 2599.42 FEET WEST OF B-7. CORNER FELL IN MARSHY AREA. WE SEARCHED FOR O.B.T'S., BUT DID NOT FIND ANY.

**APPROVED LAND CORNER**  
 P.A. 345 of 1990  
 Clare County  
 Chairman Paul S. Lephore  
 Date 12-19-94

This Corner established in Clare County Remonumentation Program.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" X 36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP IN MONUMENT BOX.

WITNESSES:  
 S10°E 33.14' - NAIL & TAG IN 6" BALSAM  
 S30°W 21.70' - NAIL & TAG IN 6" BALSAM  
 N45°W 94.07' - NAIL & TAG IN 8" MAPLE  
 S30°E 78.07' - NAIL & TAG IN 4" OAK



Signed by Mark R. Robison Date 12-19-94  
 Surveyor's Michigan License No. 27458