

SURVEY & REMONUMENTATION

JAN 23 2001

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Clare County Remonumentation

SECTION

For Corners in
Clare

(County)

Located In:

Corner Code#:

- 1. Public Land Survey T. 18N R. 5W C-5
 T. _____ R. _____
 T. _____ R. _____
- 2. Public Controlling S. _____ T. _____ R. _____
 in Section S. _____ T. _____ R. _____
- 3. Miscellaneous S. _____ T. _____ R. _____
 Property in Section S. _____ T. _____ R. _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

200000009698
 Filed for Record in
 CLARE COUNTY MICHIGAN
 CAROL MCAULAY
 On 11-29-2000 At 10:31 am.
 LAND CORNER 9.00
 OR Liber 2 Page 228 - 228

Instrument Liber Page
 200000009698 OR 2 228

#433-00

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on May 19, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO
 Cannon, 1856
 Y. Pine 18" N34°W 19 LINKS
 Y. Pine 20" S35°E, 51 LINKS
 Lapham, 1975 LCRC #209-75
 Set capped rod, 3 witnesses the same as LCRC # 22-71
 Survey, Lapham, 1979 L2. Pg. 461
 Same as LCRC #209-75
 Dist. to 1/8 corner North = 1317.00'
- C.S.R. Harper, 1902, Bk 1. Pg. 12 & Bk. 4 Pg. 14
 W.P. Stump 11" N64 1/2°W 74 LINKS
 Oak 5" S70°E, 90 LINKS
 Gray, 1995, LCRC #762-95
 Fd P.k. Nail in pavement, 4 witnesses 1 the same of LCRC #22-71
- C.S.R., Unknown, 1889, Bk. 6 Pg. 44
 No witnesses
 Survey, Sedgman, 1975 L1. Pg. 951 referenced LCRC #22-71
- Supervisor's Plat of Bearly Addition, Mosher, 1934 L2. Pg. 9
 Corner shown, no witnesses. Distance to 1/8 corner North = 1317.0'
 Survey, Lapham, 1975 L1. Pg. 975 Same as LCRC #209-75
 Dist. To 1/8 corner North = 1317.00'
- Lapham, 1971, LCRC #22-71
 Fd 3/4" Iron in T-Road intersection, 3 witnesses
 Survey, Sedgman, 1977 L2. Pg. 262 Same as LCRC #209-75
 Dist. To 1/8 corner North = 1317.00'


APPROVED LAND CORNER
P.A. 345 of 1990
Clare County
 Chairman Paul B. Le...
 Date 8-30-00

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner.
 No evidence of GLO or CSR corner found. Found P.K. Nail over 1/2" x 12" capped iron (Lapham) 2' East of centerline Bringold and on centerline of Mannsiding (E-W). Excavated to 3' deep and found 1/2" pipe with pieces of wood and clay tile. No evidence of other positions of corner. Accepted found iron as best available evidence of accepted position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set 5/8" x 36" rod with Clare County Remon Cap marked P.S. #27458.

- Witnesses:
- S30°W, 56.75' - N & T in 24" Oak (OBT)
 - S30°E, 76.18' - N & T in Power Pole (OBT)
 - S45°W, 74.78' - N & T in Power Pole (OBT)
 - N30W, 98.73' - N & T in Utility Pole (OBT)
 - N86°E, 99.75' - N & T in 14" R. Oak (OBT)

Signed by Mark R. Robison
 Surveyor's Michigan License No. 27458



11-28-2000