

SURVEY & REMONUMENTATION COMMISSION
APR 06 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
 E 10 A 0
 # 68-94
 94 NOV 28 AM 10:36

REGISTER OF DEEDS
 CLARE COUNTY
 DONNA M CARR

For corners in CLARE
 (County)

Located In: Corner Code #

- | | | | | | |
|------------------------------------|---|-----|---|----|-----|
| 1. Public Land Survey | T | 18N | R | 5W | C-7 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, MARK R. ROBISON, in a field survey on OCTOBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 11-10-1856 CANNON, POST, (1)W. PINE 34" N23°E 45 (2)HEMLOCK 15" S26°W 35 G.L.O.
 2-28-02 HARPER, (1)-ABOVE (3)W.PINE STUMP 20" S23°E 26 1/2 LKS C.S.R. 1-10
 3-29-02 HARPER, (1)-ABOVE (3)W. PINE STUMP 20" S32°E 26 1/2 LKS C.S.R. 1-12
 3-31-02 (1)-ABOVE (3)W.PINE STUMP 20" S32°E 26 1/2 LKS C.S.R. 3-14
 NOV. 1913 A.JOHNSON, (1)-ABOVE (3)W. PINE 20" S23°E 26 1/2 LKS C.S.R. 6-56
 12-19-72 VERBA S.I.P. SURVEY 1-410
 8-23-73 VERBA, SET 5/8" REBAR R.L.S. CAPPED (4)N & T POWER POLE AZ 43° 69.43'
 (5)N&T POWER POLE AZ 135° 57.15' (6) N&T OAK 12" AZ 273° 27.38' L.C.R.C. 114

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FOUND 5/8"x18" L.S CAPPED REBAR (L.S # 13603) EXCAVATED TO 3' DEPTH, FOUND 3/4" PCH PIPE BENT OVER IN BOTTOM OF HOLE. FOUND NO OTHER EVIDENCE.
 FOUND WITNESSES 4,5 & 6 AT APPROXIMATE DISTANCES (SEE NEW DISTANCES BELOW)

APPROVED LAND CORNER
 P.A. 345 of 1990
 Clare County

Chairman Paul B. Apple
 Date Nov. 23, 1994

This Corner established in Clare County Remonumentation Program.
 See dossier for detailed report.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 SET 5/8" X 36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP IN MONUMENT BOX.
 WITNESSES:
 N43°E 69.72' - NAIL & TAG IN POWER POLE (4)
 S45°E 56.90' - NAIL & TAG IN POWER POLE (5)
 WEST 27.00' - CENTER OF 15" OAK STUMP (6)
 N40°W 58.40' - NAIL & TAG IN STUB POLE
 N60°W 140.30' - NAIL & TAG IN 12" MAPLE



Signed by Mark R. Robison Date 11-23-94
 Surveyor's Michigan License No. 27458