

NOV 18 1997

CLARE COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED

For corners in

✓  
I229-97  
97 NOV -4 PM 3:15

REGISTER OF DEEDS  
CLARE COUNTY  
CAROL A. McAULAY

<u>CLARE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T19N R 5W T18N R 5W T____ R____ T____ R____	E-13 E-1
2. Property Controlling in Section	S____ T____ R____ S____ T____ R____	_____ _____
3. Miscellaneous Property in Sec.	S____ T____ R____ S____ T____ R____	_____ _____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, **MARK R. ROBISON**, in a field survey on July 1, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1838-Set Post Cor. of Sec's 32 & 33 N80W 37.60 P. Pole  
Wit.-W. Oak 10" N22W 11 S45W 35.45 15" Oak
- W. Oak 12" N38E 30 6-15-73 Lapham (132) 1-504  
G.L.O. Resurvey--no old work Found 1/2" rored  
Wit.-same as (132) 1-478
- Wit.-W. Pine 10" S38W 54 Meas. West 2611.48 to D-13  
W. Oak 8" S69E 20 7-24-73 Lapham  
04-03-1900 Harper C.S.R. 1-02 & 4-02 L.C.R.C.'s Nos. 108 & 111  
Wit.-Norway stump squared with an axe near the ground Wit.-same as (132) 1-478
- 05-04-73 Sedgman (132) 1-478 5-30-81 Sedgman (132) 659  
Set 1/2" bar, Wit.-N40E 26.37 24" Oak Fd. 1/2" bar, Wit.-same as (132) 1-478
- 12-03-82 Ward (132) 2-757  
Wit.-same as L.C.R.C.# 111
- 4-18-90 Lapham (132) 3-177  
Wit.-same as (132) 1-478
- 8-16-90 Robison--unrecorded survey  
Wit.-same as (132) 1-478 and added one witness: S80E, 36.42 - 16" Oak
- 1-24-95 Lapham L.C.R.C.# 771  
Fd. 1/2" iron, Wit.-same as 8-16-90 survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" x 18" rored. Excavated to 36 inches. Found no other evidence. Found four old witnesses.

See dossier for detailed report.

APPROVED LAND CORNER  
P.A. 345 of 1980  
Clare County  
Chairman Paul B. Leph  
Date 9-16-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13: Corner common to Sections 32 & 33, T19N, R5W, AND Sections 4 & 5, T18N, R5W, (E-1). Set 5/8" x 36" rored with 3" Clare County Monument Cap marked P.S.#27458. Accepted as best available evidence of accepted position of the corner.

- Witnesses:
- N40E 26.34', fd N&T, 30" Red Oak Stump (OBT)
  - N80W 37.60', fd N&T, Power Pole (OBT)
  - S45W 35.45', fd N&T, 20" W. Oak (OBT)
  - S66E 36.38', fd N&T, 18" R. Oak (OBT)

Signed by Mark Robison  
Surveyor's Michigan License No. 27458

Date 10-31-97

