

SURVEY & REMONUMENTATION COMMISSION
APR 06 1995
 For corners in CLARE (County)

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
 E 10 A D
 # 67-94
 94 NOV 28 AM 10:36
 REGISTER OF DEEDS
 CLARE COUNTY
 DONNA M. CARR

	Located In:	Corner Code #
1. Public Land Survey	T 18N R 5W	E-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, MARK R. ROBISON, in a field survey on NOVEMBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

NOV. 1856 CANNON, G.L.O.
 POST
 WIT.-(1)BEECH 16" N58°E 68 LKS.
 (2)BEECH 14" S60°W 75 LKS.
 2-28-02 W.W. HARPER, C.S.R. L.1-PG.10
 WIT.-(3)W. PINE STUMP 36" S74°E 1.71 CHAINS
 (4)W. OAK 10" N55°W 11 LKS.
 3-24-58 W.S. MOORE, L.3-PG.87
 WIT.-(5)B. OAK 12" N80°E 63.0'
 (6)W. OAK 18" SOUTH 54.90'

1-29-73 VERBA, L.C.R.C. #101
 FOUND 1" PINCH IRON (IDENTIFIES CORNER AS LAPHAM CORNER)
 WIT.-(5)BLAZE OAK 12" AZ 80° 63.10'
 (6)BLAZE OAK 18" AZ 180° 54.90'
 (7)NAIL & TAG BIRCH 3" AZ 85° 9.87'
 (8)NAIL & TAG BIRCH 6" AZ 165° 10.27'
 (9)NAIL & TAG BIRCH 8" AZ 262° 10.41'
 (10)NAIL & TAG BIRCH 8" AZ 350° 3.23'

12-17-75 LAPHAM, PLAT "ASSESSORS PLAT OF LINCOLN NO. 1, L.15-PG.19 & 20

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CONCRETE PLAT MONUMENT AT SECTION CORNER. FOUND CONCRETE PLAT MONUMENTS NORTH 24.72' & NORTH 107.68'. THE AREA HAS BEEN CLEARED SO ALL VERBA WITNESSES APPEAR TO HAVE BEEN DESTROYED WITH THE POSSIBLE EXCEPTION OF #5.

APPROVED LAND CORNER
 P.A. 345 of 1990
 Clare County

Chairman Paul D. Lapham
 Date Nov. 23, 1994

This Corner established in Clare County Remonumentation Program.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET SURVEYOR CAP ON 1/2" ROD IN 4"x36" CONCRETE MONUMENT FOR CLARE COUNTY REMONUMENTATION.

WITNESSES:
 N75°W 14.32' GAS WELL (FRACKLETON GRANT)
 N75°E 64.50' - NAIL & TAG (NELSON) IN 22" R. OAK
 NORTH 24.72' CONCRETE MONUMENT
 S15°W 108.55' - NAIL & TAG IN 19" OAK
 S70°W 103.24' - NAIL & TAG IN 24" OAK



Signed by Mark R. Robison

Date 11-23-94

Surveyor's Michigan License No. 27458