

SURVEY & REMONUMENTATION COMMISSION
APR 06 1995
 For corners in _____ County)

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
 E 110 A
 # 74-94
 94 DEC 29 AM 8:47
 REGISTER OF DEEDS
 CLARE COUNTY
 DONNA M. CARR

1. Public Land Survey	T18N R5W	6-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, MARK R. ROBISON, in a field survey on OCTOBER, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- SEPT. 1856, CANNON, POST (1) BEECH 10" N35°E 51 (2) W. PINE 18" S43°W 39 G.L.O. C.S.R. - NONE
- 9-15-76 SEDGMAN FOUND 1 1/2" WELL PNT. (3) MAPLE 14" S35°E 41.32' (4) OAK 8" N35°E 31.41' (5) MAPLE 8" S85°W 40.45' (132) 2-175
- 9-15-76 SEDGMAN, FOUND 1 1/2" WELL POINT (3,4 & 5)-ABOVE (132) 2-176
- 10-3-77 LAPHAM, (3,4 & 5)-ABOVE (132) 2-318
- JULY 1979 JONES, OLD WELL POINT, SURVEY (132) 2-448
- 2-24-81 WILCOX, FOUND 1 1/2" WELL POINT (6) MAPLE 4" N18°W 10.44' (7) R. OAK 8" N07°E 18.62' (4 & 5)-ABOVE (8) R. OAK 8" N83°W 16.85' (9) R. OAK 9" S11°W 2.83' L.C.R.C. 411
- 7-27-82 LAPHAM, FOUND 1 1/2" WELL POINT (3,4, & 5)-ABOVE (132) 2-740
- 6-12-87 LAPHAM, FOUND 1 1/2" WELL POINT (3,4, & 5)-ABOVE (132) 2-995
- 1-2-91 MCCLUNG, SECTION CORNER, SURVEY (132) 3-230

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1 1/2" WELL POINT STANDING 2' ABOVE GROUND AND RUSTED OFF AT GROUND LEVEL. FOUND WITNESSES NO. 4,5,6,7,8 & 9. SET 5/8" x 36" STANDARD MONUMENT IN REMAINS OF OLD WELL POINT. LEFT MONUMENT 8" ABOVE GROUND.

APPROVED LAND CORNER
 P.A. 345 of 1990
 Clare County

Chairman Paul S. Spleen

Date 12-19-94

This Corner established in Clare County Remonumentation Program.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" X 36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP IN MONUMENT BOX.

- WITNESSES:
- S85°W, 40.45' - NAIL & TAG IN 9" MAPLE (5)
 - N07°E 18.74' - NAIL & TAG IN 8" R. OAK (7)
 - N83°W 16.85' - NAIL & TAG IN 8" MAPLE (8)
 - S11°W 2.83' - NAIL & TAG IN 9" R. OAK (9)



Signed by Mark R. Robison

Date 12-19-94

Surveyor's Michigan License No. 27458