

NOV 18 1997

CLARE COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED

For corners in

CLARE  
(County)

Located In:

Corner Code #

1. Public Land Survey

T19N R 5W

1-13

T18N R 5W

1-1

T R

T R

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

#222-97  
97 OCT 15 AM 10:52

REGISTER OF DEEDS  
CLARE COUNTY  
CAROL A. McAULAY

GREENWOOD  
LINCOLN

Register of Deeds Stamp & File Number

I, MARK R. ROBISON, in a field survey on July 1, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1838 Nicholson  
Set Post Cor. Sec. 34 & 35  
Wit.-Aspen 8 N10E 07  
Birch 8 N78W 18

1-08-76 Lapham (132) 2-120 & 2-673  
Revised 3-29-76 & 8-25-81  
Found wood hub--set capped rod  
Wit.-East 3.40 6" Cedar  
West 9.60 14" Birch  
S20E 12.70 8" Cedar

6-27-12 Johnson C.S.R. 2-17 & 6-38  
Wit.-Tamarac 12" N45E 9  
Cedar 8" S45E 6  
I-1 to K-1 80.38

1-18-78 Meyers (132) 2-539  
Wit.-same as (132) 2-120

11-09-83 Ostling L.C.R.C.# 456  
Found Conc. Mon. as established in  
previous survey of Section 3  
Wit.-N40E 32.4 8" R. Oak  
S22E 42.2 5" R. Oak  
South 33.0 3/4" Rod

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found concrete monument per L.C.R.C.# 456. Found three 1976 witnesses. 1983 witnesses are not there and appear to be for a different corner. Fences North, South, and East.

See dossier for detailed report.

APPROVED LAND CORNER  
P.A. 345 of 1990  
Clare County

Chairman Paul B. Leph

Date 9-23-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13: Corner common to Sections 34 & 35, T19N,R5W, AND Sections 2 & 3, T18N, R5W, (I-1). Pulled concrete monument and set 5/8" x 36" rod with 3" Clare County Monument Cap marked P.S.#27458. Accepted as best available evidence of accepted position of corner.

Witnesses:  
East 3.40', N&T, 8" Cedar (OBT)  
West 9.60', nail & tag, 18" Birch (OBT)  
S30E 12.70', nail & tag, 12" Cedar (OBT)  
S59W 21.50', N&T, 20" W. Pine

Signed by Mark R. Robison  
Surveyor's Michigan License No. 27458

Date 10-01-97

