

REMONUMENTATION
APR 06 1995
COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
E. J. O. A. D.
71-94
94 DEC 29 AM 8:47

For corners in

CLARE
(County)

Located In:

Corner Code #

1. Public Land Survey T18N R5W M-7
T R
T R
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

REGISTER OF DEEDS
CLARE COUNTY
DONNA M. CARR

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, MARK R. ROBISON, in a field survey on NOVEMBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1838 NICHOLSON SURVEYED TOWNSHIP LINES

11-21-13 C.S.R. L.6-PG.60
WIT.-(1)PINE 36" S17°W 43 LKS.
(3)PINE 30" S55°W 67 LKS.
(4)PINE 28" N66°W 108 LKS.

3-66 LAPHAM, UNRECORDED SURVEY & NOTES OF SECTION 24.

NOES SHOW FENCE CORNER 33' N OF CORNER & 3 O.B.T.'S AS FOLLOWS:
WIT.-W.P. STUB-20" S18 1/2°W 47 LKS. O.B.T.
W.P. STUB-18" N27°E 75 LKS. O.B.T.
24" - N31°E, 119 LKS.

NOVEMBER 1856 CANNON POST
WIT.-(1)PINE 38" S17°W 47 LKS.
(2)ASPIN 12" NW 15 LKS.

L.C.R.C. - NONE
REC. SURVEYS - NONE

MUELLER (132) L.3-PG.21
NO WITNESSES.

11-23-07 JOHNSON
WIT.-NORTH 1/4 COR.-GOV'T WIT.
STATES CORNER FOUND AT
N(S.W.), I(S.E.) & E(N.E.)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

TRAVERSED FROM K-7 TO K-8 & DIAGONALLY ACROSS SECTION L-7 & M-7, FOUND K-7 TO L-7 TO BE 2652.90 (REC. 2658.2 & CALC. 2655.36 - 1966 DATA) & L-7 TO M-7 TO BE 2631.8 (REC. 2632.2). FOUND 3/4" SUCKER ROD, REPLACED WITH 5/8"x36" ROD & CLARE CO. REMONUMENTATION CAP. WE ALSO FOUND THAT ALL THE OLD WITNESSES WERE GONE. FOUND NAIL & TAG (#25861) IN OAK & CHERRY WE USED THE SAME TWO TREES, BUT USED OUR OWN NAIL & TAG. ALSO FOUND NAIL IN RED PINE, WHICH WE USED. ALSO, FOUND FENCE CORNER 33' NORTH OF CORNER AS NOTED IN UNRECORDED SURVEY.

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County

Chairman Paul D. Poppen
Date Dec. 19, 1994


This Corner established in Clare County Remonumentation Program.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" X 36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP IN MONUMENT BOX.

WITNESSES:
N0° 77.15' - NAIL & TAG IN 36" W. OAK
N45°E 67.8' - NAIL & TAG IN 10" R. PINE
S45°W 5.3' - NAIL & TAG IN 14" TWIN CHERRY
S30°W 47.6' - NAIL & TAG IN 4" MAPLE IN CLUSTER OF 5.



Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 12-19-94