

RECEIVED  
E 14 10 A E  
# 102-95  
95 OCT -3 PM 2: 49

DEC 6 1995

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION  
CLARE  
(County)

Located In:

Corner Code #

REGISTER OF DEEDS  
CLARE COUNTY  
DONNA M. CARR

- 1. Public Land Survey T 19N R 5W B-7  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, MARK R. ROBISON, in a field survey on SEPTEMBER, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-7: 1/4 Corner common to Sections 18 & 19

1857 ADAIR, BEECH 6 N88W 16, BEECH 13 S46E 29

NO CSR

MDOT-NOT ESTABLISHED

1984 LAPHAM, SET 1/2" CAPPED RE-ROD. MEAS. 2628.66 TO C-7 (132) SURVEY

- WITNESSES: N05W 73.48' COR. POST
- N15E 77.10' FENCE POST
- S15W 82.7' @ STEEL GATE POST
- SOUTH 2.5' @ ASPHALT
- (NOTES INDICATE CORNER SET S.P.M.)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NO WITNESSES. COULD NOT FIND 1/2" CAPPED RE-ROD. SET CORNER AT S.P.M. BETWEEN A-7 (2310.08') AND C-7 (2628.82')

APPROVED LAND CORNER  
P.A. 345 of 1990  
Clare County

Chairman Paul S. Teph  
Date 9-26-95

This Corner established in Clare County Remonumentation Program.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-7: 1/4 Corner common to Sections 18 & 19

SET 5/8"x36" RE-ROD WITH 3" DIAMETER CLARE COUNTY MONUMENT MARKED 1995, P.S. NO. 27458 IN MONUMENT BOX IN ASPHALT PAVEMENT.  
S 1/4 COR. ON LINE BETWEEN S/W COR. OF SEC. 18 & S/W COR. OF SEC. 17  
E 1/2 IS 2628.82 & W 1/2 IS 2310.08

ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE ACCEPTED POSITION OF THE CORNER.

- WITNESSES:
- N35°E 90.70' - FENCE POST (NAIL & TAG)
- S53°E 183.28' - POWER POLE (NAIL & TAG)
- S3°E 76.96' - BRACE FENCE POST (NAIL & TAG)
- S12°W 82.72' - COR. FENCE POST (NAIL & TAG)



Signed by Mark R. Robison

Date 10-03-95

Surveyor's Michigan License No. 27458