

DEC 6 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
E 10 11 AM
105-95
95 OCT -3 PM 2:49

For corners in MISSION
CLARE
(County)

Located In:

Corner Code #

REGISTER OF DEEDS
CLARE COUNTY
DONNA M. CARR

Register of Deeds Stamp & File Number

1. Public Land Survey	T	<u>19N</u>	R	<u>5W</u>	<u>E-7</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		R
	S		T		R
3. Miscellaneous Property in Section	S		T		R
	S		T		R

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K
2	6		5		4		3		2	
3										
4	7		8		9		10		11	
5										
6	18		17		16		15		14	
7										
8	19		20		21		22		23	
9										
10	30		29		28		27		26	
11										
12	31		32		33		34		35	
13										

I, MARK R. ROBISON, in a field survey on SEPTEMBER, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
E-7: Corner common to Sections 16, 17, 20 & 21
1856 ADAIR, HEMLOCK 18 N22W 14, HEMLOCK 22 S33E 30
10-00 HARPER, PIECE OF SLEIGH SHOE, W. PINE STUMP 24 N19 1/2W 77 1/2 CSR
MDOT BOAT SPIKE IN PAVT.
N34W 43.58' TELE. POLE
N48E 42.80' FENCE POST
S07E 33.30' FENCE POST

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND 1/2" IRON IN MON. BOX IN C. OF M-61 MDOT WITNESSES DESTROYED DURING CONSTRUCTION
MEAS. WEST 2630.6' TO D-7 AND EAST 2640.16' TO F-7

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County
Chairman Paul S. Toph
Date 10-26-95

This Corner established in Clare County Remonumentation Program.
See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
E-7: Corner common to Sections 16, 17, 20 & 21
SET 3" CLARE COUNTY REMONUMENTATION CAP MARKED 1995, P.S. #27458 ON EXISTING 1/2" IRON IN MONUMENT BOX.
ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE ACCEPTED POSITION OF THE CORNER.

WITNESSES:
NORTH 101.18' - 2" ANGLE IRON GATE POST
N10W 106.60' - 2" ANGLE IRON GATE POST
S83W 232.34' - NAIL & TAG IN POWER POLE
S55E 178.96' - NAIL & TAG IN POWER POLE



Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 10-03-95
FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 19
REVISED MAY 14, 19
REVISED JAN. 19