

REMONUMENTATION

NOV 18 1997

CLARE COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED

For corners in

CLARE
(County)

Located in:

Corner Code #

- 1. Public Land Survey

T 19N	R 5W	E-13
T 18N	R 5W	E-1
T	R	
T	R	
- 2. Property Controlling in Section

S	T	R
S	T	R
- 3. Miscellaneous Property in Sec.

S	T	R
S	T	R

#229-97
97 NOV -4 PM 3:15

REGISTER OF DEEDS
CLARE COUNTY
CAROL A. McAULAY

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, MARK R. ROBISON, in a field survey on July 1, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|--|---|
| 1838-Set Post Cor. of Sec's 32 & 33
Wit.-W. Oak 10" N22W 11
W. Oak 12" N38E 30 | N80W 37.60 P. Pole
S45W 35.45 15" Oak |
| G.L.O. Resurvey--no old work
Wit.-W. Pine 10" S38W 54
W. Oak 8" S69E 20 | 6-15-73 Lapham (132) 1-504
Found 1/2" rerod
Wit.-same as (132) 1-478 |
| 04-03-1900 Harper C.S.R. 1-02 & 4-02
Wit.-Norway stump squared with
an axe near the ground | Meas. West 2611.48 to D-13
7-24-73 Lapham
L.C.R.C.'s Nos. 108 & 111
Wit.-same as (132) 1-478 |
| 05-04-73 Sedgman (132) 1-478
Set 1/2" bar, Wit.-N40E 26.37 24" Oak | 5-30-81 Sedgman (132) 659
Fd. 1/2" bar, Wit.-same as (132) 1-478 |

- 12-03-82 Ward (132) 2-757
Wit.-same as L.C.R.C.# 111
- 4-18-90 Lapham (132) 3-177
Wit.-same as (132) 1-478
- 8-16-90 Robison--unrecorded survey
Wit.-same as (132) 1-478 and added
one witness: S80E, 36.42 - 16" Oak
- 1-24-95 Lapham L.C.R.C.# 771
Fd. 1/2" iron, Wit.-same as 8-16-90 survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" x 18" rerod. Excavated to 36 inches. Found no other evidence. Found four old witnesses.

See dossier for detailed report.

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County

Chairman Paul B. Leph

Date 9-16-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13: Corner common to Sections 32 & 33, T19N, R5W, AND Sections 4 & 5, T18N, R5W, (E-1). Set 5/8" x 36" rerod with 3" Clare County Monument Cap marked P.S.#27458. Accepted as best available evidence of accepted position of the corner.

- Witnesses:
- N40E 26.34', fd N&T, 30" Red Oak Stump (OBT)
 - N80W 37.60', fd N&T, Power Pole (OBT)
 - S45W 35.45', fd N&T, 20" W. Oak (OBT)
 - S66E 36.38', fd N&T, 18" R. Oak (OBT)

Signed by Mark Robison
Surveyor's Michigan License No. 27458

Date 10-31-97

