

DEC 1 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
E.I. LIND
107-95
95 OCT -3 PM 2:50

For corners in CLARE
(County)

Located In:

Corner Code #

REGISTER OF DEEDS
CLARE COUNTY
DONNA M CARR

- 1. Public Land Survey T 19N R 5W G-7
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Section S T R

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, MARK R. ROBISON, in a field survey on SEPTEMBER, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
G-7: Corner common to Sections 15, 16, 21 & 22

1856 ADAIR, HEMLOCK 15 N45E 25 1/2, HEMLOCK 14 S32 1/2 W 24 1/2
10-00 HARPER, A PIECE OF R.R. IRON SET AT INTER. OF HIGHWAYS CSR
MDOOT, FOUND 1" IRON BAR
WITNESSES: N45W 43.98' TELE. POLE
N38E 54.33' 23" MAPLE
S33E 60.89' FENCE CORNER

11-71 LAPHAM
WITNESSES: N60W 74.35' CMP 2--(132) SURVEY;
S45E 100.85' CMP
N25E 122.2' CMP
5-72 LAPHAM, SAME AS 11-71 SURVEY

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND 1" IRON PIPE IN MON. BOX. ALL RECORDED WITNESSES HAVE BEEN DESTROYED DURING CONSTRUCTION. MEASURED WEST 2630.96 TO F-7 & EAST 2633.44 TO H-7

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County

Chalman Paul S. Loph
Date 9-26-95

This Corner established in Clare County Remonumentation Program.
See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-7: Corner common to Sections 15, 16, 21 & 22
SET 1/2"x6" RE-ROD AND 3" CLARE COUNTY MONUMENT CAP MARKED 1995, P.S. NO. 27458 IN EXISTING 1" PIPE IN MONUMENT BOX. Poured CONCRETE AROUND PIPE & BASE OF MONUMENT. ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE ACCEPTED POSITION OF THE CORNER.

WITNESSES:
N23E 109.57' - CMP 18"
N22W 109.17' - CMP 18"
S44E 110.47' - CMP 18"
S11W 153.58' - NAIL & TAG IN POWER POLE



Signed by Mark R. Robison

Date 10-03-95

Surveyor's Michigan License No. 27458