

MARK R. ROBISON
 DEC 1 1995
 COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
 E 11 11 A T
 # 108-95
 95 OCT -3 PM 2:50

For corners in CLARE (County) Located in: _____ Corner Code # _____

1. Public Land Survey	T	<u>19N</u>	R	<u>5W</u>	<u>H-7</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Section	S	_____	T	_____	R
	S	_____	T	_____	R

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

REGISTER OF DEEDS
 CLARE COUNTY
 DONNA M. CARR

Register of Deeds Stamp & File Number

I, MARK R. ROBISON, in a field survey on SEPTEMBER, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	16	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-7: 1/4 Corner common to Sections 15 & 22
 1856 ADAIR, SUGAR 8 N35 1/2E 11, BEECH 16 N37W 15 11-83 LAPHAM, FOUND MON. BOX (132) SURVEY
 MDOT, FOUND 1" IRON PIN
 WITNESSES: N05W 35.76 24" ELM C.F.
 DUE SOUTH 34.28 FENCE CORNER C.F.
 12-75 URBANIAK, FOUND IRON IN MON. BOX
 WITNESSES: NORTH 73.2' COR FENCE POST
 SOUTH 76.4' COR FENCE POST

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" PIPE IN MON. BOX. FOUND ONE WITNESS - CORNER FENCE POST, SOUTH 76.0 FEET (PREVIOUS 76.4) MEAS. WEST 2633.4 (PREVIOUS 2633.27) TO G-7 AND EAST 2633.53 (PREVIOUS 2633.41) TO I-7. COULD NOT REMOVE PIPE

APPROVED LAND CORNER
 P.A. 345 of 1990
 Clare County
 Chairman Paul M. Lapham
 Date 9-26-95

This Corner established in Clare County Remonumentation Program.
 See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-7: 1/4 Corner common to Sections 15 & 22
 SET 1/2"x6" RE-ROD WITH CLARE COUNTY MONUMENT CAP MARKED 1995 P.S. NO. 27458 IN EXISTING PIPE IN MON. BOX. POURED CONCRETE AROUND PIPE & BASE OF MONUMENT.
 ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE ACCEPTED POSITION OF THE CORNER.

WITNESSES:
 NORTH 73.2' - NAIL & TAG IN CORNER FENCE POST (OLD)
 SOUTH 76.0' - NAIL & TAG IN CORNER FENCE POST (OLD)
 N56°W 127.83' - NAIL & TAG IN W. PINE
 S17°E 77.29' - PIPE FOR MICH. BELL UNDER-GROUND CABLE



Signed by Mark R. Robison
 Surveyor's Michigan License No. 27458

Date 10-03-95