

SURVEY & ORIENTATION

DEC 01 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
E 12 10 AM
109-95
95 OCT -3 PM 2:50

REGISTER OF DEEDS
CLARE COUNTY
DONNA M. CARR

For corners in CLARE (County) Located In: Corner Code #
1. Public Land Survey T 19N R 5W 1-7
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-L and rows 2-13. A dot is marked at the intersection of column H and row 7.

I, MARK R. ROBISON, in a field survey on SEPTEMBER, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1-7: Corner common to Sections 14, 15, 22 & 23

1856 ADAIR, BEECH 16 N52E 39, BEECH 12 S80W 41
MDOT 1" IRON PIN
WITNESSES: S45°W 46.62' FENCE CORNER
N45°W 44.84' FENCE CORNER
N45°E 49.18' FENCE CORNER

8-73 MCLUNG, NO CORNER MATERIAL (132) SURVEY
WITNESSES: N26°E 78.8' UTILITY POLE
S50°E 93.8' 20" N. PINE

12-75 URBANIAK, FOUND MON BOX (132) SURVEY
NO WITNESSES

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" IRON BAR IN MON. BOX. ALL PREVIOUS WITNESSES DESTROYED DURING CONSTRUCTION. MEASURED WEST 2633.53' (PREVIOUS 2633.41') TO H-7 AND EAST 2634.17' (MDOT 2634.36') TO J-7. COULD NOT REMOVE IRON BAR.

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County

Chairman Paul S. Leph...

Date 9-26-95

This Corner established in Clare County Remonumentation Program.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1-7: Corner common to Sections 14, 15, 22 & 23
ACCEPTED 1" DIA. IRON BAR IN MONUMENT BOX AS CLARE COUNTY MONUMENT.
ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE ACCEPTED POSITION OF THE CORNER.

WITNESSES:
S15°E 68.40' - END OF CURBING
S16°W 67.50' - END OF CURBING
N15°W 67.73' - END OF CURBING
N16°E 67.35' - END OF CURBING



Signed by Mark R. Robison

Date 10-03-95

Surveyor's Michigan License No. 27458