

**SURVEY & REMONUMENTATION**

**JAN 23 2001**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**Clare County Remonumentation**

For Corners in  
Clare  
 (County)

Located In: Corner Code#:

1. Public Land Survey T. 19N R. 5W J-11  
 T. \_\_\_\_\_ R. \_\_\_\_\_  
 T. \_\_\_\_\_ R. \_\_\_\_\_

2. Public Controlling S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_  
 in Section S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_

3. Miscellaneous S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_  
 Property in Section S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

200000010169  
 Filed for Record in  
 CLARE COUNTY MICHIGAN  
 CAROL MCAULAY  
 On 12-15-2000 At 07:44 am.  
 LAND CORNER 9.00  
 OR Liber 2 Page 292 - 292

Instrument Liber Page  
 200000010169 OR 2 292

# 497-00

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on May 9, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

GLO, Adair, 1857  
 W. Pine 30" N65°E, 18 LINKS  
 W. Pine 14" S41°W, 42 LINKS  
 Survey, Lapham, 1976 revised 1981, L2. Pg. 120 & 673  
 3/4" Iron, 3 witnesses, all same as LCRC #301-77  
 I-11 to J-11 = 2640.70  
 Survey, Meyers, 1995 not recorded  
 1/2" bar, 5 witnesses same as survey  
 L2. Pg. 631 to 640

Sedgman, 1977, LCRC #301-77  
 1 1/2" bar, 4 witnesses  
 Survey, Meyers, 1978 L2. Pg. 539  
 3/4" Iron, 3 witnesses, all same as LCRC #301-77

Survey, Sedgman, 1977 L2. Pg. 280  
 Same as LCRC #301-77  
 Survey, Dyer, 1981 L2. Pg. 631 to 640  
 1 1/2" bar, 5 witnesses, 4 are same as LCRC #301-77  
 J-11 to I-11 = 2640.42  
 J-11 to K-11 = 2641.35

**APPROVED LAND CORNER**  
 P.A. 345 of 1990  
 Clare County  
 Chairman Paul S. Popham  
 Date 12-13-00

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner.**  
 No GLO evidence found. Found 1/2" bar and 1 witness from 1981 survey. Distance to I-11 matches 1976 survey and also 1981 survey (Meas. 2640.74). Distance to K-11 matches 1981 survey (Meas. 2641.38). Accepted found iron as best available evidence of correct position of corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**  
 Set 5/8" x 36" rerod with Clare County Remon Cap marked P.S. #27458.

Witnesses:  
 South, 32.90' - Concrete monument (OBT)  
 S27°E, 37.3' - N & T in Power Pole  
 N43°E, 43.2' - N & T in Power Pole  
 N14°W, 61.65' - N & T in 18" Red Oak



Signed by Mark R. Robison  
 Surveyor's Michigan License No. 27458

Date 12/14/2000