

Surveyor  
REMONUMENTATION

CLARE COUNTY REMONUMENTATION

NOV 18 1997

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED

For corners in COMMISSION

# 223-97  
97 OCT 15 AM 10:53

CLARE  
(County)

Located In:

Corner Code #

- |                                    |            |      |
|------------------------------------|------------|------|
| 1. Public Land Survey              | T 19N R 5W | J-13 |
|                                    | T 18N R 5W | J-1  |
|                                    | T R        |      |
|                                    | T R        |      |
| 2. Property Controlling in Section | S T R      |      |
|                                    | S T R      |      |
| 3. Miscellaneous Property in Sec.  | S T R      |      |
|                                    | S T R      |      |

REGISTER OF DEEDS  
CLARE COUNTY  
CAROL A. McAULAY

GREENWOOD  
LINCOLN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, MARK R. ROBISON, in a field survey on July 1, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- |  |  |
|--|--|
| 1838 Nicholson<br>Set qr. Sec. Post<br>Wit.-Hemlock 8" N71E 28<br>Hemlock 7" N15W 63 | 1-08-76 Lapham (132) 2-120 & 2-673<br>Revised 3-29-76 & 8-25-81<br>Found Concrete Monument<br>Wit.-S60W 5.40 8" Maple<br>N80E 8.40 6" Maple<br>N05E 16.60 6" Maple |
| 6-27-12 Johnson C.S.R. 2-17 & 6-38<br>Wit.-Pine Stump 36" N60E 12                    |  |

1-18-78 Meyers (132) 2-539  
Found Concrete Monument  
Wit.-S60W 5.40 8" Maple  
N80E 8.40 6" Maple  
N05E 16.60 6" Maple

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found concrete monument and 1976 witnesses. Corner is 27 feet North & 5 feet East of new fence. Found no other evidence at fence corner. Accepted monument.

See dossier for detailed report.

APPROVED LAND CORNER  
P.A. 345 of 1990  
Clare County

Chairman Mark R. Robison  
Date 9-23-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13: 1/4 Corner common to Section 35, T19N, R5W, AND Section 2, T18N, R5W, (J-1). Removed concrete monument and set 5/8" x 36" rerod with 3" Clare County Monument Cap marked P.S.#27458. Accepted as best available evidence of the accepted position of the corner.

Witnesses:  
S64W 5.40', N&T, 9" Maple (OBT)  
N80E 8.40', nail & tag, 7" Maple (OBT)  
N05E 16.60', nail & tag, Twin 7" Maple (OBT)  
N65W 18.75', N&T, 8" Maple

Signed by Mark R. Robison  
Surveyor's Michigan License No. 27458

Date 10-01-97

