

**SURVEY & REMONUMENTATION**

**MAR 24 2000**

**LAND CORNER RECORDATION CERTIFICATE**

**Filing Requirement of Act 74, Mich. P.A. 1970**

**SECTION**

**Clare County Remonumentation**

For Corners in  
Clare

(County)

Located In:

Corner Code#:

- 1. Public Land Survey T. 19N R. 6W C-13  
T. 18N R. 6W C-1  
T. \_\_\_\_\_ R. \_\_\_\_\_ C-\_\_\_\_\_
- 2. Public Controlling S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_  
in Section S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_
- 3. Miscellaneous S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_  
Property in Section S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

199900010464  
Filed for Record in  
CLARE COUNTY MICHIGAN  
CAROL MCAULAY  
On 12-03-1999 At 02:36 pm.  
LAND CORNER 9.00  
OR Liber 2 Page 102 - 102

Instrument 199900010464 OR Liber Page 2 102

# 390-99

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on October 5, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

1838 Rousseau  
East 77.0 Set Cor Secs. 31 & 32  
Swp. Ash 8 - N8E 25  
Swp. Ash 18 - N14W 15

3-13-74 McClung, (132) 2-205  
1/2" Pipe w/cap  
S54E 14.85 14" Cedar  
S30W 15.25 15" Maple  
N45W 38.00 16" Maple

3-08-74 McClung, (132) 1-934  
Same as (132) 2-205

2-75 McClung, (132) 1-933  
Same as (132) 2-205

2-26-75 McClung LCRC #189  
Set 1/2" pipe by prop. measurement  
Same as (132) 2-205 exc cedar is stump

01-06-86 Roser LCRC #514 & Dwg. #31-93124  
Fd & accepted 1/2" pipe by McClung  
added DNR Mon & Ced. Post  
N50W 30.0 11" Maple  
N25E 15.2 15" Maple  
N65E 15.0 11" Ced Stp.  
S70W 37.8 16" Maple  
Meas. E 2612.62 to D-13  
Meas. W 2597.36 to B-13

11-11-86 Lapham, (132) 2-980  
Same as LCRC #514

**APPROVED LAND CORNER**  
P.A. 245 of 1990  
Clare County

Chairman Paul S. Lapham  
Date 12-01-99

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

See dossier for detailed report.

Found DNR monument and cedar post 1.5' S.W. Found all 1986 witnesses. Did not find 1974 witnesses. DNR witnesses are to blazed face of trees.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Accepted DNR Monument as Clare County Remon Monument. Accepted as best available evidence of the accepted positions of the corner.

Witnesses:

- N25°E 15.90 Set N & T in 24 x 12 x 6 Maple (OBT)
- S77°E 54.65 Set N & T in 22 x 10 x 6 Maple
- S70°W 38.37 Set N & T in 20" Maple (OBT)
- N50°W 30.50 Set N & T in 15" Maple (OBT)

Signed by Mark R. Robison  
Surveyor's Michigan License No. 27458



Date 12-1-99