

**CLARE County Remonumentation**  
**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>CLARE</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T20N R06W T19N R06W T ___ R ___ T ___ R ___	E-13 <u>E-1</u> _____ _____
2. Property Controlling in Section	S ___ T ___ R ___ S ___ T ___ R ___	_____ _____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___ S ___ T ___ R ___	_____ _____

RECEIVED  
 E IV  
 # 288-98  
 98 NOV 18 AM 9:56  
 REGISTER OF DEEDS  
 CLARE COUNTY  
 CAROL A. NEAULAY

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Mark R Robison, in a field survey on May 26, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate**

This is a single corner common to T20N, R06W E-13 and T19N, R06W E-1

- A. Description of original monument and accessories and/or subsequent restoration:
- E-13: 1838 Nicholson  
 Set Post Cor Sec 32 - 33  
 Wit-W. Oak 16 N16W 12  
 W. Pine 18 N18E 19
  - 10-2-72 Lapham LCRC#65  
 Wit-same as 5-17-72 survey
  - 1856 Coleman Set Post Cor Sec 32 & 33  
 Wit-W. Pine 12 N46E 28  
 W. Pine 24 N39 1/2W 29  
 Note: Coleman resurveyed from S 1/4 Cor Sec 31 to meander post on W side river in Sec 34.
  - 10-27-86 Lapham (132) 2-966  
 Wit-same as 5-17-72 survey  
 E-13 to E-12 2638.34
  - 5-17-72 Lapham unrec survey & sketch  
 Fd 1" Bar  
 Wit-S50E 63.70 8" Pine  
 S35W 73.35 4" Oak  
 N80W 60.80 4" Oak  
 E-13 to F-13 2613.40
  - 2-7-92 Weitherell unrecorded survey  
 1" Iron  
 Meas East 2614.44 to 1/4 Cor

**SURVEY &  
 REMONUMENTATION**  
 NOV 25 1998  
 SECTION

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- E-13: Found 1" Iron in Monument Box one foot East of centerline of M-61. Found all three 1972 witnesses but two were dead. Measured North 2638.20 (Recorded 2638.34) feet to 1/4 Corner.
- See dossier for detailed report.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- E-13: Set 5/8" x 36" rod with Clare County Remonumentation Cap marked P.S.#27458 in Monument Box. Accepted as the best available evidence of the accepted position of the corner.

Witnesses:  
 S50E 63.70', nail & tag, 14" J. Pine (OBT)  
 N27W 97.68', nail & tag, 9" Maple (Clump of 4)  
 N80E 50.68', nail & tag, 11" Elm  
 N22E 122.70', nail & tag, 4" W. Pine



**APPROVED LAND CORNER**  
 P.A. 345 of 1990  
 Clare County  
 Chairman [Signature]  
 Date 9-8-98

Signed by [Signature]  
 Surveyor's Michigan License No. 27458

Date 11-16-98