

**CLARE County Remonumentation**  
**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED  
 E ✓  
 #289-98  
 98 NOV 18 AM 9:56  
 REGISTER OF DEEDS  
 CLARE COUNTY  
 CAROL A. MAULAY

For corners in

<u>CLARE</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T20N R06W T19N R06W T____R____ T____R____	F-13 <u>F-1</u> _____ _____
2. Property Controlling in Section	S____T____R____ S____T____R____	_____ _____
3. Miscellaneous Property in Sec.	S____T____R____ S____T____R____	_____ _____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Mark R Robison, in a field survey on May 26, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate**

This is a single corner common to T20N, R06W  
 F-13 and T19N, R06W F-1

- A. Description of original monument and accessories and/or subsequent restoration:
- F-13: 1838 Nicholson Set 1/4 Sec Post  
 Wit-W. Pine 12 S20W 62  
 W. Pine 10 S15E 1.15
  - 1856 Coleman Set 1/4 Sec Post  
 Wit-Aspen 8 N55E 45 & Aspen 10 N69W 58  
 Note: Coleman resurveyed from S 1/4 Cor Sec 31 to meander post on W. side river in Sec 34.
  - circa 1900 Unknown CSR 6-221  
 Wit-S Pine 10 N51W 90 & Y Pine 10 N45E \_\_\_\_\_
  - 5-17-72 Lapham (132) 1-292  
 Set 1/2" Bar (2613.40 to E-13)  
 Wit-N15E 31.65 10" Pine  
 S70W 40.81 8" Pine
  - 10-02-72 Lapham LCRC#65; Wit-same as 5-17-72 survey
  - 5-1-85 McClung (132) 3-74 Fd 1/2" rod  
 Wit-same as above
  - 6-17-88 McClung (132) 3-100; refers to previous survey
  - 2-11-92 Wetherell Fd 1/2" C.I.  
 LCRC#658 & unrecorded Plat of Survey  
 Wit-S4E 26.15' 6" W. Pine  
 S63E 10.40 7" W. Pine  
 S75W 40.81 11" W. Pine  
 N09W 22.6' 3" W. Pine

**SURVEY &  
 REMONUMENTATION**  
 NOV 25 1998  
 SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 F-13: Found 1/2" x 18" C.I. and all 1972 and 1992 witnesses.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 F-13: Set 5/8" x 36" rod with Clare County Remonumentation Cap marked P.S.#27458. Accepted as best available evidence of the accepted position of the corner.

Witnesses:  
 S75W 40.81', nail & tag, 16" W. Pine (OBT)  
 S04E 26.15', nail & tag, 8" W. Pine (OBT)  
 S63E 10.40', nail & tag, 9" W. Pine (OBT)  
 N09W 22.60', nail & tag, 5" W. Pine (OBT)



**APPROVED LAND CORNER**  
 P.A. 345 of 1990  
 Clare County  
 Chairman [Signature]  
 Date 9-8-98

Signed by [Signature]  
 Surveyor's Michigan License No. 27458

Date 11-16-98