

**SURVEY & REMONUMENTATION**

**MAR 24 2000**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**Clare County Remonumentation**

**SECTION**

For Corners in  
Clare  
 (County)

1. Public Land Survey	T. <u>19N</u> R. <u>6W</u>	<u>F-13</u>
	T. <u>18N</u> R. <u>6W</u>	<u>F-1</u>
	T. _____ R. _____	_____
2. Public Controlling	S. _____ T. _____ R. _____	_____
in Section	S. _____ T. _____ R. _____	_____
3. Miscellaneous	S. _____ T. _____ R. _____	_____
Property in Section	S. _____ T. _____ R. _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

199900009770  
 Filed for Record in  
 CLARE COUNTY MICHIGAN  
 CAROL MCAULAY  
 On 11-10-1999 At 01:30 pm.  
 LAND CORNER 9.00  
 OR Liber 2 Page 49 - 49

Instrument 199900009770 OR Liber Page 2 49

# 360-99

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on ~~11-12-99~~ **2-11-99**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

This is a single corner common to T19N, R6W, F-13 and T18N, R6W, F-1

A. Description of original monument and accessories and/or subsequent restoration:

1838 Rousseau  
 Set 1/4 Sec. Post  
 Swp. Ash 12, N80E 20  
 Swp. Ash 3, S12W 13

01-86 Roser LCRC #509 & Dwg. No 31-93124  
 Fd & accepted sucker rod for S1/4 Cor added RLS cap.  
 N55W 98.28 P.P.  
 N85E 348.0 16" W. Pine  
 North 9' C.L. E-W Grd. Rd  
 North 33' Set Ced. Post  
 East 10' Old WW fence N'y  
 Meas. W 2617.69 to E-13  
 Meas. E 2617.34 to G-13

02-92 McClung, (132) 3-351  
 Same as LCRC #509

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:  
 See dossier for detailed report.

Found 5/8" x 24" female sucker rod, bent on top, on S. Side of E-W sand road across marsh area. Meas. East 2617.14' (D.N.R. 2617.34) to G-13. Found three D.N.R. witnesses. The P.P. and D.N.R. post falls in water in marsh.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Set 5/8" x 36" reroed with Clare Co. Remon Cap marked P.S. #27458. Accepted as best available evidence of the accepted position of the corner.

Witnesses:  
 North 32.68' Face of 6 x 6 DNR Post (OBT)  
 N84°E 348.54' Set N & T in 24" W. Pine (OBT)  
 S83°W 331.00' Set N & T in 18" W. Pine  
 N55°W 98.28' Accepted D.N.R. distance to P.P. (OBT)

**APPROVED LAND CORNER**  
 P.A. 345 of 1990  
 Clare County

Chairman Paul S. Loph  
 Date 9-29-99

Signed by Mark R. Robison  
 Surveyor's Michigan License No. 27458



Date 11-8-99