

CLARE County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
 98 #291-98
 NOV 18 AM 9:56
 REGISTER OF DEEDS
 CLARE COUNTY
 CAROL A. McLAULAY

For corners in

CLARE Located in: Corner Code #
 (County)

1. Public Land Survey T20N R06W H-13
 T19NR06W H-1
 T R
 T R
 2. Property Controlling S T R
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Mark R Robison, in a field survey on May 26, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

This is a single corner common to T20N, R06W H-13 and T19N, R06W H-1

A. Description of original monument and accessories and/or subsequent restoration:

H-13: 1838 Nicholson
 Set 1/4 Sec Post
 Wit-Maple 12" N20E 14
 Maple 16 N17W 15

1856 Coleman
 Wit-Hemlock 14 N56E 29
 Y. Pine 12 N26W 117

Note: Coleman resurveyed from S 1/4 Sec 33 to Meander Post on W. Side river in Sec 34.

12-15-76 Ostling LCRC#277&Plat of Survey
 Set corner at squared tree believed to be previously used by Gourdie-Fraser in survey of Section 3 & conforms generally to U.S. Notes to swamps, etc.
 Set DNR Mon
 Wit-N68E 20.6 20" W. Pine
 S20E 17.15 6" R. Oak

9-15-92 Gourdie-Fraser File Drawing
 Fd DNR Monument
 Wit-N70E 20.93 20" W. Pine
 N40E 35.10 12" R. Pine
 N20W 16.02 16" Oak
 S30E 17.44 8" Oak

**SURVEY &
 MONUMENTATION**

NOV 25 1998

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13: Found DNR Monument and both witnesses. Found three 1992 witnesses.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13: Accepted DNR Monument as Clare County Remonumentation Monument. Accepted as best available evidence of the accepted position of the corner.

Witnesses:
 N68E 21.35, nail & tag, 28" W. Pine (OBT)
 S20E 17.38, nail & tag, 12" R. Oak (OBT)
 N15W 16.12, nail & tag, 20" Twin Oak (OBT)
 N82W 22.48, nail & tag, 18" R. Oak



APPROVED LAND CORNER
 P.A. 345 of 1990
 Clare County

Chairman [Signature]
 Date 9-8-98

Signed by [Signature]
 Surveyor's Michigan License No. 27458

Date 11-16-98