

CLARE County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
 #274-98
 98 NOV 18 AM 9:55

REGISTER OF DEEDS
 CLARE COUNTY
 CAROL A. HEAULAY

For corners in

<u>CLARE</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T19N R06W	J-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Mark R Robison, in a field survey on May 20, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

J-7: 1856 Coleman
 39.57 Set 1/4 Sec Post
 Wit-Hemlock N20E 17
 Maple 4 S13W 7

8-20-75 Lapham LCRC#213
 Wit-same as (132) 1-985

MSHD No data

4-18-75 Lapham (132) 1-985
 Fd 1/2" pipe in Mon box
 Wit-N10E 77.10 C/L Conc R/W Mon
 N05E 102.05 P.P.
 N20W 134.23 10" J. Pine

**SURVEY &
 REMONUMENTATION**

NOV 25 1998

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-7: Found 1/2" Pipe in Monument Box 2.6 feet South of Centerline of Highway. Found all 1975 witnesses. Measured East 2639.04 to K-7. Measured West 2639.06 (recorded 2639.05) to I-7. Could not remove 1/2" pipe to search for additional material.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-7: Accepted 1/2" Pipe in Monument Box as Clare County Remonumentation Monument. Accepted as best available evidence of the accepted position of the corner.

Witnesses:
 N10E 77.10' Center of Concrete Right-of-Way Marker (OBT)
 N05E 103.00', nail & tag, P.P.
 N20W 134.23', nail & tag, 14" Jack Pine (OBT)
 N30W 123.15' Center of 4" Steel Gate Post



APPROVED LAND CORNER
 P.A. 345 of 1990
 Clare County
 Chairman [Signature]
 Date 9-22-98

Signed by [Signature]
 Surveyor's Michigan License No. 27458

Date 11-16-98