

MAR 24 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Clare County Remonumentation

SECTION

For Corners in
Clare

(County)

Located In:

Corner Code#:

- 1. Public Land Survey T. 19N R. 6W J-13
T. 18N R. 6W J-1
2. Public Controlling in Section S. T. R.
3. Miscellaneous Property in Section S. T. R.
4. Lot No. Recorded Plat
5. Private Claims

199900009757
Filed for Record in
CLARE COUNTY MICHIGAN
CAROL MCAULAY
On 11-10-1999 At 01:30 pm.
LAND CORNER 9.00
OR Liber 2 Page 46 - 46

Instrument 199900009757 OR Liber Page 2 46

#357-99

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on August 11, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

Table with 13 rows and 13 columns labeled A through M. Contains numerical data points for survey locations.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

This is a single corner common to T19N, R6W, J-13 and T18N, R6W, J-1

A. Description of original monument and accessories and/or subsequent restoration:

- 1838 Rousseau Set 1/4 Sec Post Hemlock 16 N71E 27 Hemlock 17 S40W 18
11-29-89 Lapham LCRC #596 Fd 1/2" pipe w/cap on top North 30.2 Fence Post N45E 36.3 Fence Post East 25.38 Fence Post N38W 40.5 Fence Post
8-24-06 & 1-23-07 Johnson CSR 4-66, 4-81, 6-183 Cedar Post 10" N62E 6

10-3-94 Robison, (132) 3-474
Fd 1/2" Capped Pipe
Same witnesses as LCRC #596

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County


Chairman Paul S. Lapham

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner Date 9-29-99
See dossier for detailed report.

Found 1" x 24" iron bar surrounded by broken glass to depth of 18". Found two 1989 witnesses. Corner falls on extended C.L. gravel road S & W. Excavated to 24" and hit large stones. Meas. W 2629.04 to I-13. Found fence line North and East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set 5/8" x 28" rerod with Clare Co. Remon Cap marked P.S. #27458. Accepted as best available evidence of the accepted position of the corner.

- Witnesses:
N05°E 29.45 Set N & T in RR tie F. Post (OBT)
N85°E 25.18 Set N & T in RR tie F. Post (OBT)
S44°W 61.70 Set N & T in 6" Cherry
N60°W 59.88 Set N & T in 10" Elm



Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 11/8/99