

CLARE County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

CLARE
 (County)

Located in:

Corner Code #

- | | | | |
|------------------------------------|---|-----------|-----|
| 1. Public Land Survey | | T19N R06W | K-7 |
| | | T R | |
| | | T R | |
| | | T R | |
| 2. Property Controlling in Section | S | T R | |
| | S | T R | |
| 3. Miscellaneous Property in Sec. | S | T R | |
| | S | T R | |

RECEIVED
 #275-98
 98 NOV 18 AM 9:55
 REGISTER OF DEEDS
 CLARE COUNTY
 CAROL A. HOULAY
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Mark R Robison, in a field survey on May 20, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		13		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- | | | |
|--|---|---|
| K-7: 1856 Coleman GLO
Set Post Cor Sec 13, 14, 23, 24
Wit-Ced 12" N34E 15
Hem 12" S34W 18 | 4-05-73 Urbaniak LCRC#98
Fd Mon Box
Wit-N34W 62.8 Cor F. Post
N31E 61.4 Cor F. Post
S22E 48.8 Road Sign | 4-10-84 Robison
Wit-same as LCRC#213 |
| circa 1960 Koivisto MSHD
Fd 1" Iron rod
Wit-S22E 48.85 Rd Sign
N31E 61.37 Cor. Fe. Post
N34W 62.77 Cor. Fe. Post | 8-20-75 Lapham LCRC#213
Fd 1/2" Bar in Mon Box
Wit-North 5.20 Cen Hwy
S40W 40.94 Set C.I. at back of curb at curb joint
S40E 40.94 Set C.I. at back of curb at curb joint | |
| 1966 Erickson MSHD
Wit-Same as 1960 MSHD | | |

SURVEY & REMONUMENTATION

NOV 25 1998

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- K-7:** Found 1" Iron rod in Monument Box 5.2 feet South of centerline of highway. Found all 1975 witnesses. Could not remove 1" Iron rod to search for additional material. See dossier for detailed report.
 Measured South 2564.62 (recorded 2565.11) to K-8.
 Measured East 2649.30 to L-7. Measured West 2639.04 to J-7.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-7:** Accepted 1" Iron rod in Monument Box as Clare County Remonumentation Monument. Accepted as best available evidence of the accepted position of the corner.

- Witnesses:
 S40W 40.94' C.I. at Back of Curb at Joint (OBT)
 S40E 40.94' C.I. at Back of Curb at Joint (OBT)
 S22E 49.85' Road Sign Post
 N31E 173.40', nail & tag, 13" Red Pine



APPROVED LAND CORNER

P.A. 345 of 1990
 Clare County

Chairman Donald L. [Signature]
 Date 9-22-98

Signed by [Signature]
 Surveyor's Michigan License No. 27458

Date 11-16-98