

CLARE County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
CLARE
 (County)

Located in: Corner Code #

- | | | |
|------------------------------------|------------|------------|
| 1. Public Land Survey | T20N R06W | L-13 |
| | T19N R 06W | <u>L-1</u> |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |

RECEIVED
 # 295-98
 98 NOV 18 AM 9:57
 REGISTER OF DEEDS
 CLARE COUNTY
 CAROL A. MCAULAY
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Mark R Robison, in a field survey on May 28, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

This is a single corner common to T20N, R06W L-13 and T19N, R06W L-1

- A. Description of original monument and accessories and/or subsequent restoration:
- L-13: 1838 Nicholson
 Set 1/4 Sec Post
 Wit-Tamarack 12 N44E 09
 Tamarack 10 S28W 10
 - 12-15-76 Ostling LCRC#274&Plat of Survey
 Set corner by proportionate meas, MPOL, between section corners. Fits swamp edges acceptably, but cannot identify US evidence at corner.
 Set DNR Mon and red-top Post
 Wit-N72W 17.3 4" Cedar
 S20E 11.5 4" Cedar
 - CSR 2/126
 circa 1900(?) Unknown Iron Rod
 Wit-Elm 16" SE 50.7
 Elm 24" SW 64.8

SURVEY & REMONUMENTATION
 NOV 25 1998
 SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 L-13: Found DNR Monument and both witnesses.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 L-13: L-13: Accepted DNR Monument as Clare County Remonumentation Monument. Accepted as the best available evidence of the proper method of re-establishment of the corner.

- Witnesses:
- N72W 17.30', nail & tag, 6" Cedar (OBT)
 - S20E 11.50', nail & tag, 6" Cedar (OBT)
 - N20W 10.92', nail & tag, 10" Spruce
 - S58E 13.03', nail & tag, 16" W. Pine



APPROVED LAND CORNER
 P.A. 345 of 1990
 Clare County
 Chairman [Signature]
 Date 9-22-98

Signed by [Signature]
 Surveyor's Michigan License No. 27458

Date 11-16-98