

CLARE County Remonumentation  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

REGISTERED  
 E.V.  
 #276-98  
 98 NOV 18 AM 9:55  
 REGISTER OF DEEDS  
 CLARE COUNTY  
 CAROL A. HEAULAY

For corners in

CLARE Located in: Corner Code #  
 (County)

1. Public Land Survey T19N R06W L-7  
 T R  
 T R  
 T R

2. Property Controlling S T R  
 in Section S T R

3. Miscellaneous S T R  
 Property in Sec. S T R

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Mark R Robison, in a field survey on May 20, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		11		32		33		34		35		36	
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate**

A. Description of original monument and accessories and/or subsequent restoration:

- L-7: 1856 Coleman GLO  
 Set 1/4 Sec Post on true line  
 Wit-Aspen 6 N30E 12  
 Aspen 4 S33W 17
- 1966 Erickson MSHD  
 Fd nail in road--Set 1" Iron  
 Wit-N03E 43.82 5" Poplar  
 S45E 55.84 15" Elm  
 S20E 39.25 13" Elm  
 Meas 2604.94 East to Sec Cor

**SURVEY &  
 REMONUMENTATION**

NOV 25 1998

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- L-7: Found 3/4" Pipe in Monument Box. Did not find 1966 witnesses. Measured 2649.30 West to K-7. Measured 2605.24 East to M-7 (MSHD recorded 2604.94). Corner is 3 feet East of fences North and South.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-7: Accepted 3/4" pipe as Clare County Remonumentation Monument. Accepted as best available evidence of the accepted position of the corner.

Witnesses:  
 N01E 74.24' Center of Concrete Right-of-Way Marker  
 N13W 104.82', nail & tag, 11" Elm  
 N48W 165.74', nail & tag, 18" W. Pine  
 S04W 76.88', nail & tag, Corner Fence Post



**APPROVED LAND CORNER**  
 P.A. 345 of 1990  
 Clare County  
 Chairman [Signature]  
 Date 9-22-98

Signed by [Signature]  
 Surveyor's Michigan License No. 27458

Date 11-16-98