

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 19 N. R. 6 W.	H-1, I-1
2. PROPERTY CONTROLLING IN SECTION 3	T. 19 N. R. 6 W.	2
3. MISCELLANEOUS PROPERTY IN SECTION 3	T. 19 N. R. 6 W.	J-1/2
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 3, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on November 2, 1976, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- H-1 Set corner at squared tree, believed previously used in subdivision of Section 3 by Gourdie-Fraser, Traverse City. Fits their survey of record, and conforms generally to U.S. notes to swamps, etc.
- I-1 Set corner on line between section corner east and M.C. west for latitude, and on line over ¼ and section corner north between 34 and 35 for departure.
- 2 Set by standard survey procedure for the subdivision of sections.
- J-1/2 Set on section line at riverbank. U.S. left bank M.C. would fall about 80' east, in river. No government evidence.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-1	I-1	2	
Set DNR Monument	Set DNR Mon. red-top post 16' E	Set 3/8" hex rod & red-top post	
20" W. Pine N68°E 20.6	7" J. Pine N50°E 39.55	8" Oak N58°E 13.9	
6" R. Oak S20°E 17.15	4" J. Pine N65°E 26.75	10" Oak N75°W 35.5	
J-1/2			
Set 3/8" hex rod & red-top post			
2" W. Pine N27°E 4.60			
2" W. Pine N43°W 11.15			
Riverbank East 18'			


SIGNED BY Kenneth J. Ostling DATE 12-15-76

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____



SURVEYOR'S MICHIGAN REGISTRATION NO. _____ CLARE COUNTY

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET