

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 19 ^{N.} R. 6 ^{W.}	J-3, K-3, L-3
2. PROPERTY CONTROLLING IN SECTION <u>1</u>	T. 19 ^{N.} R. 6 ^{W.}	16
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} R. _____ ^{E.}	_____
4. LOT NO. _____	RECORDED PLAT _____	
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 1, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- J-3 Set by proportionate measurement, MPOL, between section corners. Could not identify a previous corner or U.S. evidence.
- K-3 Set by double proportionate measurement between corners ½ mile north and 1 mile E-S & W. Fits U.S. calls east, north and west but no evidence of previous corner.
- L-3 Set corner by proportionate measurement, MPOL, between section corners. No evidence of a previous corner.
- 16 Set by standard survey procedure for subdivision of sections.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-3	K-3	L-3
Set DNR mon. & red-top post	Set DNR mon. & red-top post	Set DNR mon. & red-top post
11" Balsam S76°W 14.65	13" Oak S05°E 45.1	19" R. Pine N45°E 45.70
10" Maple N10°E 15.45	11" Oak S42°E 71.9	7" Maple N42°W 51.65
	18" R. Pine S20°E 94.3	
		16
		Set 3/8" hex rod & red-top post
		3" R. Pine N43°E 19.6
		3" R. Pine N60°W 20.25

SIGNED BY *Kenneth J. Ostling* DATE 12-15

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____

CLARE COUNTY