

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 19 ^{N.} <input checked="" type="radio"/> , R. 6 ^{W.} <input checked="" type="radio"/>	K-1, K-4, L-1
2. PROPERTY CONTROLLING IN SECTION <u>1</u>	, T. 19 ^{N.} <input checked="" type="radio"/> , R. 6 ^{W.} <input checked="" type="radio"/>	1
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ ^{N.} _____, R. _____ ^{E.} _____ ^{W.} _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 2, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-1 Set corner at fence corner, beside large cedar post said by local resident to have been placed at location of square stake. Very old fence line west and south. Unable to identify any previous BT's, but fits government calls acceptably.
- K-4 Set by proportionate measurement MPOL, between section corners. No evidence of previous corner.
- L-1 Set corner by proportionate measurement MPOL, between section corners. Fits swamp edges acceptably, but cannot identify U.S. evidence at corner.
- 1 Set by standard survey procedure for subdivision of sections.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1	K-4	L-1
Set DNR Monument	Set DNR Mon. & red-top post	Set DNR Mon. & red-top post
5" R. Oak S55°W 62.7	8" Cedar N23°W 29.65	4" Cedar N72°W 17.3
6" J. Pine S68°E 14.3	6" Cedar S83°W 53.6	4" Cedar S20°E 11.5
3" J. Pine N14°W 12.8		
	1	
	Set 3/8" hex rod & red-top post	
	8" Cedar S23°E 15.35	
	4" Cedar N89°E 13.1	


SIGNED BY *Kenneth J. Ostling* DATE 12-15-76

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____ CLARE COUNTY

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET