

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>19</u> N. <u>0.</u> , R. <u>6</u> W. <u>0.</u>	<u>E-6; G-6</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____, R. _____ S., R. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____, R. _____ S., R. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on February 5, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- E-6 - Fd & accepted 1/2" rod for W 1/4 Cor. of Section 16; fits 3-MSHD wits. Fits U.S. stream tie 129'-north (to N. side of stream).
- G-6 - Fd & accepted 2"x2"x25" angle iron for E 1/4 Cor. of Sec. 16; believed to be position of Schaaf Corner. Schaaf notes (Jan. 1940) indicate he had Milton Nye's 1857 correction to Francis Coleman's 1856 dependent re-survey corner; that is more Coleman's corner 72 1/2 links south to be mid-way and on line between NE & SE of Sec. 16. J. Sedgman used this corner to subdivide Section 16.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

	<u>E-6</u>		<u>G-6</u>	
Fd 1/2" iron rod w/RLS cap;			Fd 2"x2"x25" angle iron; added	
added ced post w/loc tag			DNR mon & cedar post	
12" Oak	N67°W	31.24'	19" Black Oak	N45°W 20.21'
SW cor of W			22" Black Oak	N10°E 49.90'
wingwall(bridge)	N3°W	105.2'	13" Black Oak	
SE cor of E			(in clump)	S60°E 10.30'
wingwall(bridge)	N12°E	109.4'	Ctr trail NW&SE	Due E 25'
Ctr N-S trail	Due E	7'		

SIGNED BY Carl F. Roser 01-06-86 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

REDDING TWP
CLARE COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

Reproduced by the State of Michigan