

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 19 <sup>N.</sup> / <sub>S.</sub> , R. 6 <sup>X.</sup> / <sub>W.</sub>	E-10; F-10; F-11
2. PROPERTY CONTROLLING IN SECTION _____	T. _____, <sup>N.</sup> / <sub>S.</sub> , R. _____, <sup>X.</sup> / <sub>W.</sub>	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____, <sup>N.</sup> / <sub>S.</sub> , R. _____, <sup>E.</sup> / <sub>W.</sub>	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on February 6, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:  
C continued

~~Decree of a Court of law: \_\_\_\_\_~~

<u>F-11</u>		
Set DNR Mon & ced post		
7" B cherry	N25°E	78.1'
8" B oak	N60°E	74.3'
4" W pine	N80°W	119.0'
ctr N-S trail	Due W	29'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:  
E-10 - Fd old 1½" pipe (18" out of ground) for W¼ cor of Sec. 28. This pipe fits M. Schaaf Wits (Aug. 1939) whose notes indicate he had original corner here. Fit U.S. stream tie to south. A ½" rod is 0.5' east. The Schaaf pipe is a restoration of 1856 dependent resurvey who reestablished old (original) qtr sec cor here.

F-10 - Estab. ctr of Sec. 28 at intersection of ¼ lines.

F-11 - Reestab. S¼ cor of Sec. 28 at proportionate measurement to 1856 G.L.O. resurvey between SE & SW cor's of S-28. GLO-E¼ mi. 40.00 ch, W¼ mi. 39.70 ch. Approx. cor of old fn remains S'ly & E'ly is 71'± S & 13'± W. An Arthur Johnson corner position from his two wits (no cor fd) is S14°07'W 46'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>E-10</u>	<u>F-10</u>
Fd old 1½" pipe; added ced post	Set 5/8" x 34" rerod w/RLS cap & ced post w/loc tag
12" B Oak N10°W 54.03'	17" Ced N25°E 2.9'
7" Maple S85°E 31.69'	8" Ced S50°E 5.1'
9" Maple S55°W 13.82'	9" Ced S30°W 5.6'
Ct E-W dirt Due S 25'	9" Ced N35°W 16.5'
rd	
Ctr 2' creek Due S 309'	
NWly	


SIGNED BY Carl F. Roser 01-06-86 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ REDDING TWP.  
 CLARE COUNTY

Reproduced by the State of Michigan