

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. 19 N. 06 W.		A-1, A-2, B-1, B-2
2. PROPERTY CONTROLLING IN SECTION _____, T. _____ N. S., R. _____ E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, CARL F. ROSER, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 01/22, 1986, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

C. (CONTINUED)

XX

<p>B-1</p> <p>FD 1 1/2" IRON PIPE. ADDED CED POST W/LOC TAG. *32" B CHERRY N80°E 36.61' *50" COTTONWOOD S30°E 45.00' * 9" R PINE S60°W 62.48' *COR FN POST NORTH 9.37'</p>	<p>B-2</p> <p>DROVE 5/8" X 34" REROD. 9" R PINE N50°W 30.5' 8" R PINE N55°E 45.9' 8" R PINE S55°W 32.9' CTR N-S DIRT RD DUE E 6' SET CED POST W/LOC TAG. DUE E 33'</p>
--	--

*R.L.S. J. WILCOX WIT TREES

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- A-1 FD & ACCEPTED 1/2" REROD IN 3" TILE (BURIED 3") FOR NW COR OF SEC 6. E-W DIRT RD IN CURVE IS SOUTH 11'±. COR IS IN LINE WITH OLD FN'S TO N & S.
- A-2 FD OLD 3" TILE (VERTICAL) & ACCEPTED FOR W 1/4 COR OF SEC 6. FITS TWO (1940) MARCUS SCHAAF (DECEASED DEPT FORESTER & RLS) N.B.T.S. SCHAAF NOTES SAY HE HAD TWO U.S. (G.L.O.) B.T. STUMPS. OLD FN COR (FN REMAINS N-S-W) IS 16'±N & 2'±E.
- B-1 FD & ACCEPTED 1 1/2" IRON PIPE FOR N 1/4 COR OF SEC 6. CTR OF E-W DIRT RD IS S 13'±. COR IS IN LINE WITH CTR OF DIRT RD LOOKING SOUTH.
- B-2 ESTAB CTR OF SEC 6 AT INTERSEC OF ONE-QUARTER LINES.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>A-1</p> <p>FD 1/2" REROD W/RLS CAP #14102 AND 3" TILE. *POWER POLE DUE N 25.00' *SW COR BRICK HSE N30°E 91.9' *E. END STEEL DWY CULV N60°W 46.0' SET CED POST W/ LOC TAG. DUE S 33'</p>	<p>A-2</p> <p>FD TILE & ADDED 5/8" X 34" REROD W/RLS CAP & CED POST W/LOC TAG. 25" Oak N45°E 17.3' 6" CHERRY S20°E 16.9' 3" CHERRY S75°W 21.3'</p>
--	--

*R.L.S., J. WILCOX WITS.

SIGNED BY Carl F. Roser 01-27-86 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____



(SEAL)
REDDING TWP
CLARE COUNTY