

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>19</u> N. <u>6</u> R. <u>6</u> W.	<u>E-11;</u>
2. PROPERTY CONTROLLING IN SECTION <u>29</u>	T. <u>19</u> N. <u>6</u> R. <u>6</u> W.	<u>15;16</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ R. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 15, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

	<u>16</u>	
Drove 5/8" x 34" rerod	w/RLS cap & ced post w/loc tag	
2" Maple	N20°E	27.4'
24" Old W. Pine	N25°E	21.4'
Stmp		
7" R. oak	S40°W	47.5'
8" W. oak	N70°W	80.9"

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

E-11 - Recovered 2" pipe & 2" x 5" ax cut pine stk that fits 3-M. Schaaf N.B.T. stumps. Schaaf (Conservation Dept. Forestry Chief & RLS - now deceased) notes, Aug. 1939, indicate he had both U.S.B.T. (G.L.O.) stumps of which the pine stump remains are still evident. Drove DNR monument on 1" x 36" pipe inside fd 2" pipe.
15 - Drove 5/8" x 34" rerod for SW corner of SE 1/4 of SW 1/4 of Sec. 29; midway & on line between recovered Schaaf SW & S 1/4 cors of S-29. Fd Schaaf pipe mon standing (broke off top-bottom still in ground) N73°47'E, 3.5' fd. RLS, Don Fluke rerod, S13°00'W, 112.37'.
16 - Drove 5/8" x 34" rerod for SE corner of SW 1/4 of SE 1/4 of Sec. 29; midway & on line between recovered Schaaf SE & S 1/4 cors of S-29. Fd Schaaf pipe mon. (broke off from Timber cutting) S20°W, 4.1'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

	<u>E-11</u>	
Fd old 2" pipe; added DNR mon & ced post		Drove 5/8" x 34" rerod w/RLS cap & ced post w/loc tag
2" Maple	N35°W 26.98'	Sly edge Muskegon Riv. Due N 31'
9" J. Pine	N75°E 4.16'	7" sugar maple N85°E 4.5'
13" B. Oak	S60°E 47.00'	2" Balsam S20°E 13.2'
10" J. Pine	S20°E 36.86'	6" Sugar maple S10°W 42.1'
Ctr trail	Due W 107'	

SIGNED BY Carl F. Roser 01-06-86 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

REDDING TWP
CLARE COUNTY

Approved by the State of Michigan